

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

NOTICE INVITING e-TENDER

MALDA REGIONAL OFFICE

N.I.T. NO.: RM/MRO/e-TENDER/ 2025-26/10; Dt. 26.11.2025

Online percentage rate e-Tender in two part for the under mentioned work is invited by the Regional Manager, Malda Regional Office, WBSEDCL from eligible, bonafide, resourceful and experienced contractors of State/Central Govt., State/Central Govt. undertaking, Statutory Bodies constituted under the statute of State/Central Govt. for under mentioned work as per specified terms, conditions and specifications.

Name of the work	Estimated Amount (Rs.)(including 1% cess & excluding GST)	Completion Time	Earnest Money Deposit (Rs.)
Construction of security room, car parking shed, surrounding area development with paver block along with some gardening, installation of main gate along with gate pillar, painting of boundary wall including Electrical wiring of the building at Chanchal Administrative Building under Chanchal Division.	Total= Rs.36,38,127.38/- (1. Civil works:Rs.26,34,814.09/- + 2.Electrical works:Rs.10,03,313.29/-)	90 (Ninety) days From date of Site Handover.	Rs. 72,800.00/-

- 1. Intending bidders should download the tender documents from the website https://www.wbtenders.gov.in directly with the help of Digital Signature Certificate (DSC). Necessary Earnest Money Deposit (EMD) should be remitted separately through either online mode or in the form of Bank Guarantee (BG) in full on any schedule commercial bank in the annexed format and the same should be documented and scan copy of the aforesaid documents is to be uploaded through said website as per schedule stated in Sl. No. 6(Details of which has been narrated in the Instruction to the bidders). The last date for submission of physical copy of EMD via Bank Guarantee (if EMD in the form of bank guarantee is opted) will be upto 30.12.2025 upto 14.00 hrs. Partial payment through online mode and remaining submission through BG is not allowed. EMD collected via online mode will be settled automatically from etendering portal maintained by National informatics Centre (NIC) wherein EMD for rejected or unsuccessful bids shall be refunded in the bank account of participating bidders directly from NIC Portal. However, for successful bidder the Earnest Money will be converted into Security Deposit.
- 2. Both **Technical Bid** and **Financial Bid** are to be submitted concurrently duly digitally signed by the Bidder through the website https://wbtenders.gov.in. (Details of which has been narrated in 'Instruction to Bidders') as per Schedule stated in Sl.No.8.
- 3. **Eligibility criteria for participation in tender:** The pre-qualification criteria will be subject to bidder's fulfillment of the qualification criteria set forth and stipulated hereunder & substantiated by authentic and relevant information and details. The bidders shall also have experience and proven track record in taking up and completion of the work of magnitude and nature similar to the items as mentioned hereunder.
- 4. Technical Requirement:



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

The bidder must have successfully completed **similar works**(*defined below) for Civil &Electrical (composite and separate)work during last **07**(**Seven**) years (i.e. upto 30.10.2025) under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government. Value of work done i.r.o Civil & Electrical works will be evaluated separately in case of composite works. The criteria for similar completed works will be as follows:

I. <u>Three similar</u> completed works each costing not less than the amount equal to <u>40%</u> of the estimated cost.

OR

II. <u>Two similar</u> completed works each costing not less than the amount equal to <u>50%</u> of the estimated cost.

OR

III. One similar completed work costing not less than the amount equal to 80% of the estimated cost.

(*Civil:The bidder must have successfully completed similar type of work in last 7 years(i.e.upto 30.10.2025)under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government.

*Electrical: The bidder must have successfully completed Building Wiring, Installation of Lighting Equipment in last 7 years (i.e. upto 30.10.2025) under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government.)

Satisfactory Completion Certificate indicating estimated amount and/or Ordered Amount, Value of work-done and Date of completion of the work and detail communicational address along with contact details of the Client should be submitted by the Bidder. Completion Certificate from the concerned Executive Engineer/District Engineer/Divisional Engineer or equivalent rank and above will be treated as valid credential. The bidder is to upload the LOA/Execution Order/PO in full along with the BOQ showing the full description of items in respect of the work for which completion certificate is being uploaded. Delay in completion of work, if any, must be mentioned in completion certificate along with the reason

(A) Statutory/Non-Statutory requirements:

All categories of prospective Bidders (<u>Firm/Entity</u>)shall have to submit valid copies of the following documents (All the documents must be in the name of the <u>Firm/Entity</u> applying as prospective bidders):

- I. Professional Tax Registration Certificate/Registration No.(P. Tax Registration Certificate/ Enrollment Certificate as applicable), current professional tax payment certificate along with payment challan.
- II. P.F. Registration Certificate/No. along with challan for the month of August or onwards.
- III. GST Registration Certificate/No with up to date return/challan, [Monthly/Quarterly applicable].
- IV. E.S.I. Registration certificate/No. with challan for the month of August or onwards.
- V. PAN Card and Income Tax Return for last three Assessment Years.
- VI. Valid Electrical Contractor's License issued by the Licensing Board, Government of West Bengal/India under Act with valid Electrical Supervisor's Certificate of Competency (SCC) Part No. 1,2,3,4,6A,6B,7A, 7B, 11& 12issued by the Licensing Board, Government of West Bengal/India (current engagement of electrical Supervisor at prospective bidders firm needs to be established).



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

VII. Valid up-to-date Trade License in respect of the prospective Bidder: VIII. Registration Certificates of Firms/ Entities,

a. Proprietorship Firm (Valid Trade License),

b. Partnership Firm (Valid Partnership Deed, Valid Trade License),

- c. Ltd Company (Incorporation certificate i.e. MOA and AOA, Valid Trade License),
- d. Co-operative Society (Society Registration copy, valid Trade License).

NB: Any MOU/Temporary Agreement/Joint Ventures/Consortium/ Any other arrangement to constitute an Entity having no statutory Registration Certificates (Non-Permanent Establishment) beyond the above entities [mentioned in VIII(a) to (d)] for the purpose of applying as prospective bidder will not be considered as valid document.

- IX. Performance as prime contractor applying as prospective bidder for execution of similar nature of work for last seven years will only be considered.
- X. Information regarding any past and current litigation with WBSEDCL/WBSETCL/Govt/PSU in which the bidder is involved, the party's concerned and disputed amount.
- XI. Neither prospective Bidder nor any of the constituent partners had been be barred to participate in any Tender by any Government Department/Semi-Govt/Govt Undertakings/ Enterprise etc. during the last 5 (five) years prior to the date of this NIT. Such debarring will be considered as disqualification towards eligibility. A declaration on Rs.100.00/- Non-Judicial Stamp duly notarized by Notary Public, in this respect has to be furnished by the prospective bidders.
- XII. The bidder shall submit reports on the financial standing i.r.o. solvency of Bidder (Company/Firm) as certified by bankers, audited annual reports on accounts with auditors' certificate for company registered under Companies Act and Tax Audit Report for Partnership Firms for last three preceding Financial Years.
- XIII. Net worth for the each of the last 03(three) Financial Years should be positive. Net worth means the sum total of the paid up capital and free reserves (excluding reserves created out of revaluation) reduced by aggregate value of accumulated losses (including debit balance in profit and loss account for current year) and intangible assets.
- XIV. The bidder's Minimum Average Annual Turnover (MAAT) for last 03 (three) Financial Years shall not be less than 30% of the estimated cost per year.
- XV. The working capital of the bidder in the preceding year of bid submission shall not be less than 30% of the estimated cost per year.
- XVI. In case documents certifying credit facility from a scheduled bank is submitted, the requirement given in Clause No.XIV above, shall be judged by adding available credit facility and working capital taken together.
- **XVII.** Annual Audited Financial Report for last 3 (three) years to be submitted for verification in respect of bidders for whom audit of accounts is mandatory (3CA/3CB and particulars are reported in the Form 3CD u/s 44AB of Income Tax Act'1961 are to be submitted). For those whose audit of accounts is not mandatory, they shall submit copy of IT returns along with related enclosures for last fiveyears.
- XVIII. The prospective Bidders or any of their constituent partner shall neither have abandoned any work nor any of their contract have been rescinded during the last 5 (five) years. Such abandonment or rescission will be considered as disqualification towards eligibility. A declaration on Rs.100.00/- Non-Judicial Stamp duly notarized by Notary Public, in this respect has to be furnished by the prospective bidders. (Non-statutory Documents)
 - XIX. No conditional/incomplete/inadequate/wrong submission of Tender Documents and facts



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

willbeacceptedunderanycircumstancesandnofurtherprayerforconsiderationwill be entertained.

- XX. Details of Eligibility criteria for participation in tender for Electrical Works are mentioned in Instruction to Bidders (SECTION-A) under the head A-2. (Sl. No. vii, viii & ix) Non statutory cover containing of Eligibility criteria for participation in tender.
- 5. The **FINANCIAL OFFER** of the prospective bidder will be considered only if the **TECHNICAL BID** of the Bidder is found qualified by the WBSEDCL. The decision of the WBSEDCL will be final and absolute in this respect. The list of Qualified Bidders of Technical Bid will be displayed in the website.
- 6. No mobilization advance and secured advance will be allowed.
- 7. A prospective Bidder shall be allowed to participate in the tender either in the capacity of individual or as a partner of firm, Society, Company, Registered Unemployed Engineers Co-operative Society/Registered Labour Co-operative Society. If found applied severally in a single job, all his offers will be rejected for that job.
- 8. Bid shall remain valid for a period not less than 180 (one hundred twenty) days from the date of opening of Financial Bid. If the bidder modifies/withdraws the bid during the interval between the deadline for submission of bids and the expiry of the period of bid validity, the bid will be cancelled with forfeiture of earnest money deposit (EMD).

9. **Date and Time Schedule:**

1.	Date of uploading of NIT & other Documents (Publishing	03.12.2025 AFTER 11:00 hrs
	Date)	
2.	Documents download/sell start date (online)	03.12.2025 AFTER 11:00 hrs
3.	Bid submission starting date (online)	03.12.2025 AFTER 11:00 hrs
4.	Pre Bid Meeting	04.12.2025 AFTER 15:00 hrs
5.	Document download end/Bid submission closing date (online)	29.12.2025 UP TO 13:00 hrs
6.	End Date of submission of EMD (Online)	29.12.2025 UP TO 13:00 hrs
7.	End Date of physical submission of EMD (Offline) NB-if	30.12.2025 UP TO 14:00 hrs
	EMD is submitted through BG	
8.	Techno-commercial bid opening date	31.12.2025 AFTER 14:00 hrs
9.	Techno-commercially qualified bidders' list uploading date	To be notified later
10.	Price bid opening date	To be notified later

- 10. The Bidder at the their own responsibility is encouraged to visit and examine the site of works and its surroundings and obtain all information that may be necessary for preparing the Bid and entering into a contract for the work as mentioned in the Notice Inviting Tender. The cost of visiting the site shall be at the Bidder's own expense.
- 11. The WBSEDCL reserves the right to accept or reject any offer without assigning any reason whatsoever and is not liable for any cost that might have been incurred by any Bidder at any stage of Bidding.
- 12. Prospective applicants are advised to note carefully the minimum qualification criteria as mentioned in 'Instructions to Bidders' stated in Section 'A' before tendering the bids.
- 13. Exemption from deposition of earnest money deposit (EMD) shall not be allowed under any circumstances.
- 14. Conditional / Incomplete tender will not be accepted under any circumstances.

We/t bengal/tate Electricity Di/tribution Company Ltd. (A Govt. of West Bengal Enterprise) MBSFDIL

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue. Malda, WB- 732101. E-mail: rm.malda@wbsedcl.in

VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in CIN: U40109WB2007SGC113473

Regd. Office of WBSEDCL:

14. Conditional / Incomplete tender will not be accepted under any circumstances. 15.

The intending Bidders are required to quote the rate online only through tendering process.

16. During scrutiny, if it comes to the notice of the tender inviting authority that the credential or any other paper found incorrect / manufactured / fabricated, that bidder would not be allowed to participate in the tender and that application will be rejected without any prejudice.

MALDA REGIONAL OFFICE

Canvassing in connection with the tender is strictly prohibited in the Tender submitted by the 17.

Contractor.

The eligibility of a Bidder will be ascertained on the basis of the documents submitted by a Bidder 18. in support of eligibility criteria. If any document submitted by a Bidder is incorrect/ manufactured / fabricated or false at any stage, his Tender will be out rightly rejected and legal action will be taken against him.

19. The participating bidders may please note that the successful bidder shall have to submit an Indemnity Bond along with Agreement in the prescribed format before commencement of the work.

The WBSEDCL does not bind itself to accept the lowest bidder and reserves the right to reject any or all tender(s) or to split the whole work to more than one contractor without assigning any reason whatsoever.

The WBSEDCL reserves the right to cancel the N.I.T. due to unavoidable circumstances and no claim in this respect will be entertained.

Sd/-

Dated: 26, 11, 2025

Regional Manager Malda Regional Office **WBSEDCL**

Memo no: RM/MRO/Civil/e-Tender/ 901(1-7) Copy forwarded for kind information and needful action please to:

1. The Chief Engineer (Dist.-North), WBSEDCL, Siliguri-734001.

The Zonal Manager, Malda Zonal Office, Malda, WBSEDCL. 2.

The Manager (HR&A)/ (F&A), Malda Regional Office, WBSEDCL. 3.

The Divisional Manager, Chanchal Division, WBSEDCL. 4.

The Assistant Engineer (Civil), Malda Regional Office, WBSEDCL. 5.

Copy for Notice Board/Tender file / Office copy.

Regional Manager Malda Regional Office WBSEDCL



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

INSTRUCTION TO BIDDERS SECTION-A

- **1. General guidance for Tendering:** Instructions/Guidelines for electronic submission of the tenders online have been annexed for assisting the contractors to participate in e-Tendering.
- **2. Registration of Contractor:** Any contractor willing to take part in the process of e-Tendering will have to be enrolled & registered with the Government e-Procurement System of West Bengal, through logging onto http://www.wbtenders.gov.in(the web portal), the contractor is to click on the link for e-Tendering site as given on the web portal.
- **3. Digital Signature Certificate (DSC):**Each contractor is required to obtain a Class-II or Class-III Digital Signature Certificate (DSC) for submission of tenders from the approved service provider of the National Informatics Centre (NIC) on payment of requisite amount. Details are available at the Web Site stated in Clause 2 above. DSC is given as a USB e-Token.
- **4. Downloading of Tender documents:** The contractor can search & download N.I.T. & Tender Document(s) electronically from computer once he logs on to the website mentioned in clause 2 using the Digital Signature Certificate. This is the only mode of collection of Tender Documents.
- **5. Participation in more than one work:** A prospective bidder shall be allowed to participate in the job either in the capacity of individual or as a partner of a firm, Society, Company, Ltd Company (Incorporation certificate i.e. MOA and AOA, Valid Trade License), Co-operative Society (Society Registration copy, valid Trade License). If found applied severally in a single job, all his offers will be rejected for that job.
- **Submission of Tenders:** General process of submission: Tenders are to be submitted online to the website stated in Cl.2 above, in two folders at a time, one in Technical Proposal & the others Financial Proposal before the prescribed date & time using Digital Signature Certificate (DSC). The documents are to be uploaded in the form of virus scanned copy duly Digitally Signed. The uploaded Documents will get encrypted (transformed into non-readable formats).

A. Technical Proposal:

A-1.Statutory Parts:

- a) To be submitted in "Drafts" folder:
- i. Cost of Tender Document: No Cost.
- ii. **Earnest Money Deposit (EMD):** The amount of Earnest Money Deposit (EMD) shall be deposited online as prescribed in the NIT. **The bidder shall select the tender to bid and initiate payment of EMD.** Documentary evidence of online EMD payment (if any) should be uploaded in draft folder during submission of bid.
- iii. Following payment options are available for paying EMD amount:
 - I. Net-banking through Payment Gateway.
 - II. RTGS/NEFT Payment: On selection of RTGS/ NEFT as the payment mode, the e-



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

Procurement portal will show a pre-filled challan having the details to process RTGS/NEFT transaction. The bidder will print the challan and use the prefilled information to make RTGS/NEFT payment using his bank account. Once the payment is made, the bidder will come back to the e-procurement portal to continue the bidding process after expiry of a reasonable time to enable the RTGS/NEFT process to be completed.

III. Submission of the EMD through Bank Guarantee: For submission of EMD in the form of Bank Guarantee, the bidder will have to opt for EMD exemption in e-tender web portal and upload scanned copy of BG in the EMD exemption document upload section. Physical copy of BG shall be submitted at the Office of the Regional Manager, Malda Region within scheduled date and time as mentioned in NIT Notice.

iv. General Instructions for Online Payment:

- **I.** The bidder will have to mandatorily pay through Net-banking facility once Net banking mode is opted for payment.
- **II.** Status of NEFT/RTGS payment through Challan for a bid may take time for bank settlement which is updated in 24 Hrs. (approx.). As such bidders opting to pay through NEFT/RTGS mode shall make payment well before 24 Hrs. to avoid any complicacy.
- **III.** In case actual EMD amount as per NIT is more than the one shown in E-tender Portal, bidders will have to opt for NEFT/RTGS mode (challan mode). In that case the total actual EMD amount is to be paid only through NEFT/RTGS mode (challan mode).
- **IV.** The bank account used for payment of EMD by the bidders shall be maintained operative until the completion of tendering process. All refunds will be made mandatorily to the Bank A/c from which the payment of EMD has been initiated.

v. Refund/ Settlement of EMD Amount:

- **I.** For unsuccessful bidders, EMD amount submitted against the tender shall be refunded automatically, through an automated process, by NIC portal on receipt of updated status of any bid.
- **II.** For successful bid(s), EMD will be refunded from WBSEDCL authority after completion of tendering process and following due procedures.
- **III.** The bank account used for payment of EMD by the bidders shall be maintained operative until the completion of tendering process. All refunds will be made mandatorily to the Bank A/c from which the payment of EMD has been initiated.
- **IV.** For any queries related to payments and refunds, bidders will have to communicate with ICICI Customer Support, viz. 33-4O267512/13 since payment gate way facility used by E-tender portal is maintained by ICICI.
- **v.** Successful bidder(s) shall have to mandatorily create vendor id through WBSEDCL Web Portal Vendor Corner if not created earlier.

b) To be submitted in "NIT" folder:

- i. Notice Inviting e-Tender(NIT).
- ii. Technical Specifications.
- iii. Addenda/Corrigenda: if published.

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Note: Bidders are to keep track of all the Addendum/Corrigendum issued with a particular tender and upload all the above duly digitally signed along with the NIT. Tenders submitted without the Addendum/Corrigendum will be treated as informal and liable to be rejected.

c) To be submitted in "Forms" folder:

- i. Declaration of Black Listing / Holiday Listing (as per Form-IX, X).
- ii. Certificate regarding summary statement of yearly turnover (Form I).
- iii. Form II evidence of access to or availability of credit facilities if applicable.
- iv. Form-XI- Litigation/ Arbitration against WBSEDCL.
- v. Form-XII Proforma for Undertaking.
- vi. Form-XIII- Format of Letter of Bid.
- vii. Annexure I Declaration by the bidder.
- viii. Form III statement of similar type of works (civil & electrical) executed during last 07 (seven) years.

Note: All the above documents are to be uploaded duly digitally signature.

A-2. Non statutory cover containing:

- i. Professional Tax Registration Certificate/No. (P. Tax Registration Certificate/ Enrollment Certificate as applicable), current professional fees payment certificate along with payment challan.
- ii. P.F. Registration Certificate/No. along with up to date challan of last month,
- **iii.** GST Registration Certificate/No. with up-to-date return/ challan for last three months, (Monthly/Quarterly as applicable).
- iv. E.S.I. Registration Certificate with up to date challan of last month.
- v. PAN and Income Tax Return for last three Assessment Years.
- vi. Valid up-to-date Trade License in respect of the prospective Bidder.
- vii. Valid Electrical Contractor's License issued by the Licensing Board, Government of West Bengal/India under Act with valid Electrical Supervisor's Certificate of Competency (SCC) Part No. 1,2,3,4,6A,6B,7A,7B,11& 12issued by the Licensing Board, Government of West Bengal/India (current engagement of electrical Supervisor at prospective bidders firm needs to be established).
- viii. Have sufficient credential of similar nature of Civil & Electrical Works.
- **ix.** Have to give necessary documentary evidence for presence and engagement of licensed Electrical Supervisor for supervision and execution of work.

Note: All the documents stated in Sl. No. vii, viii and ix above for execution of electrical works is to be uploaded along with tender.

- **x.** The bidder shall submit reports on the financial standing i.r.o. solvency of Bidder (Company/Firm) as certified by bankers, audited annual reports on accounts with auditors' certificate for companies registered under Companies Act and Tax Audit Report for Partnership Firms for last 3(Three) Financial Years.
- **xi.** Net worth for the each of the last 03 (three) Financial Years should be positive. Net worth means the sum total of the paid up capital and free reserves(Excluding reserves created out of revaluation) reduced by aggregate value of accumulated losses (including debit balance in profit and loss account for current year) and intangible assets.
- xii. The bidder's Minimum Average Annual Turnover (MAAT) for last 03 (three) Financial



MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Years shall not be less than 30% of the estimated cost per year.

xiii. The working capital of the bidder in the preceding year of bid submission shall not be less than 30% of the estimated cost per year.

xiv. In case documents certifying credit facility from a scheduled Bank is submitted, the requirement given in clause no (xiii) shall be judged by adding available credit facility and working capital taken together.

Annual Audited Financial Report for last 3 (three) years to be submitted for verification in respect of bidders for whom audit of accounts is mandatory (3CA/3CB and particulars are reported in the Form 3CD u/s 44AB of Income Tax Act'1961 are to be submitted). For those whose audit of accounts is not mandatory, they shall submit copy of IT returns along with related enclosures for last five years.

xvi. Registration Certificates of Firms/Entities:

a. Proprietorship Firm (Valid Trade License),
b. Partnership Firm (Valid Partnership Deed, Valid Trade License),
c. Ltd Company (Incorporation certificate i.e. MOA and AOA, Valid Trade License),

d. Co-operative Society (Society Registration copy, valid Trade License).

xvii. Credential of completed works as mentioned here are: The bidder must have successfully completed similar works* for Civil &Electrical (composite and separate) work during last 07(Seven) years (i.e. upto 30.10.2025) under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government. Value of work done i.r.o Civil & Electrical works will be evaluated separately in case of composite works. The criteria for completed similar works will be as follows:

1. Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.

OR

2. Two similar completed works each costing not less than the amount equal to 50% of the estimated cost.

OR

3. One similar completed work costing not less than the amount equal to 80% of the estimated cost.

(*Civil: The bidder must have successfully completed similar type of work in last 7 years (i.e. upto 30.10.2025) under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government.

*Electrical: The bidder must have successfully completed Building Wiring, Installation of Lighting Equipment in last 7 years (i.e. upto 30.10.2025) under the authority of State/Central Government, State/Central Government undertaking, Statutory Bodies constituted under the statute of Central/State Government.)

Satisfactory Completion Certificate indicating estimated amount and/or Ordered Amount, Value of work-done and Date of completion of the work and detail communicational address along with contact details of the Client should be submitted by the Bidder. Completion Certificate from the concerned Executive Engineer/District Engineer/Divisional Engineer or equivalent rank and above will be treated as valid credential. The bidder is to upload the LOA/Execution Order/PO in full along with the BOQ showing the full description of items in respect of the work for which completion certificate is being uploaded. Delay in completion of work, if any, must be mentioned in completion certificate along with the reason.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Note: The bidder must have full-fledged set up for executing similar projects in power utility.

B. Financial Proposal (in one cover/folder):

It contains Bill of Quantities (BOQ). The rate to be quoted in the BOQ on "percentage basis" in the space marked for quoting rate (either excess, less or at par i.e. 0.00%). Quoted rate will be encrypted in the B.O.Q. under Financial Bid.

(Only downloaded copies of the above documents are to be uploaded, virus scanned and digitally signed by the bidder).

Note: - Failure of submission of any of the above-mentioned documents (as stated in A1, A2 and B) will render the tender liable to summarily rejected for both statutory & non statutory cover.

THE ABOVE STATED NON-STATUTORY/TECHNICAL DOCUMENTS SHOULD BE ARRANGE IN THE FOLLOWING MANNER.

Click' the check boxes beside the necessary documents in the 'My Document' list and then 'click' the tab "Submit Non-Statutory Documents" to send the selected documents to Non-Statutory folder. Next Click the tab "Click to Encrypt and upload" and then click the "Technical" Folder to upload the Technical Documents (Statutory documents).

Sl. No.	Category Name	Sub Category Description	Details
A	Certificates	Certificates	 PAN. E.P.F. Document. G.S.T. Document. P. Tax Document. E.S.I. Document. Audited Annual Report on Accounts documents. ITR Document. (Annual Audited Financial Report for last 3 (three) years to be submitted for verification in respect of bidders for whom audit of accounts is mandatory (3CA/3CB and particulars are reported in the Form 3CD u/s 44AB of Income Tax Act'1961 are to be submitted). For those whose audit of accounts is not mandatory, they shall submit copy of IT returns along with related enclosures for last five years). Credit facility from any schedule bank to make short fall in working capital. Electrical Contractor's License issued under Act with valid Electrical Supervisor's Certificate of Competency (current engagement of electrical Supervisor at Prospective bidders' firm needs to be established).



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

	ı	ı	
			1. Proprietorship Firm (Valid Trade License).
			2. Partnership Firm (Valid Partnership Deed, Valid Trade
		Company Details – I	License).
В	Company		3. Ltd Company (Incorporation certificate i.e. MOA and AOA,
	Details		Valid Trade License).
			4. Co-operative Society (Society Registration copy, Valid
			Trade License).
			1. Necessary documents regarding Similar nature of work done which is applicable for eligibility in this tender (As per
	Credential	ntial Credential 1	Clause no.3.A of NIT).
			· ·
		n Declaration	1. Declaration of Black Listing / Holiday Listing (Form-IX,X).
			2. Certificate Regarding Summary Statement of Yearly
			Turnover (Form-I).
D	Declaration		3. Form-II - Evidence of Access to or Availability of Credit
			Facilities If Applicable.
			4. Form-XI- Litigation/ Arbitration against WBSEDCL.
			5. Form-XII - Proforma for Undertaking.
7. Annexure - I – Declaration by the b 8. Form– III - Statement of Similar Typ		6. Form-XIII- Format of Letter of Bid.	
			· · · · · · · · · · · · · · · · · · ·
		8. Form— III - Statement of Similar Type of Works (Civil &	
			Electrical) Executed During Last 07 (Seven) Years.

7. **Opening of Tender:**

A. Technical Proposal:

- i. Technical proposals will be opened by authorized representatives of WBSEDCL from the web site stated using their Digital Signature Certificate.
- ii. Intending bidders may remain present if they so desire.
- iii. Covers (folder) statutory documents will be opened first & if found in order, cover(Folder) for non-statutory documents will be opened. If there is any deficiency in the statutory documents the tender will be summarily rejected.
- iv. Decrypted (transformed in to readable formats) documents of the non-statutory cover will be downloaded & handed over to the authorized representatives of WBSEDCL.
- v. Uploading of summary list of technically qualified bidders:
 - a. Pursuant to scrutiny & decision of the authorized representatives of WBSEDCL the summary list of eligible bidders & the serial number of works for which their proposal will be considered will be uploaded in the web portals.
 - b. While evaluation the authorized representatives of WBSEDCL may summon any of the bidder & seek clarification / information or bidder/s may be asked for producing original hard copy/s of any of the documents already submitted & if these are not produced within the stipulated time frame, their proposals will be liable for rejection.

B. Financial Proposal:

i. The financial proposal should be one cover (folder) containing bill of quantities (BOQ)



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

the contractor is to quote the rate [Percentage Excess/Less/AT PAR (0.00%)] online in the space marked for quoting rate in the BOQ.

ii. Only downloaded copies of the above documents are to be uploaded virus scanned & Digitally Signed by the contractor.

MALDA REGIONAL OFFICE

8. **Parties Who May Bid:**

- i. Invitation of bid is open to the eligible bidders of Indian origin and the bid will be made in the basis of local competitive bids(LCD).
- ii. All materials to be supplied and services to be rendered under this contract shall be accepted from bidders fulfilling the eligibility/capability criteria.
- iii. A prospective bidder shall be allowed to participate in the job either in the capacity of individual or as a partner of the firm, Ltd Company (Incorporation certificate i.e. MOA and AOA, Valid Trade License), Co-operative Society (Society Registration copy, valid Trade License). If any of the bidders is found to have applied severally in a single job all his applications will be summarily rejected for that job.

9. **Responsibility of Bidders:**

- i. WBSEDCL will not assume any responsibility regarding information gathered, interpretations or conclusions made by the bidder or regarding information, interruption or deductions the bidder may derive from the data furnished by the WBSEDCL. Verbal agreement or conversation with any officer, employee of WBSEDCL either before or after the execution of the contracts, shall not affect or modify any of the terms or obligations contained in the contract.
- ii. It shall be the responsibility of the bidders to determine and to satisfy themselves by such means as they consider necessary or desirable as to all matters pertaining to this contract including in particular all factors that may affect the cost, duration and execution of the works. It must be understood and agreed that such factors have properly been investigated and considered while submitting the bid.
- iii. Claim, whatsoever, including those for financial adjustment to the contract awarded under these specifications and documents will not be entertained by the purchaser. Neither any change in time schedule of contract nor any financial adjustments arising thereof shall be permitted by the purchaser, which are based on the back of such clear information of its effect on the cost of the contract to the bidder.
- iv. The bidder is expected to examine carefully all instructions, conditions, forms, schedules terms, annexure, specifications and drawings in the bidding document. Failure to comply with the requirements of bid submission will be at the bidder's own risk. Bids, which are determined to be not substantially responsive to the requirement of the bidding document, will be rejected.
- 10. **Cost of Bidding:** The bidder shall bear all cost associated with the preparation and submission of their bid and WBSEDCL in no case shall be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process.
- 11. **Clarification of Bidding Document:** Should there be any discrepancy or obscurity in the meaning of any clauses of the bid document or if there be any query of the intending bidder, the bidder shall set forth



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

in writing such discrepancies, doubt, obscurity or queries and submit the same to WBSEDCL, marked to the **Regional Manager, Regional office, WBSEDCL**, the date specified for this purpose. The clarification given in the pre- bid discussion shall be final and binding on the bidder.

12. **Bid Prices:**

- (a) The bidder shall quote their price in the appropriate format in percentage excess/at par/ less the estimated price.
- (b) The quoted price should be firm. There will be no price variation during the pendency of the contract period or thereafter. Bidders are in no way allowed to get any escalation of price against this contract.
- (c) Prices indicated in the schedule of prices deemed to include all the levies/duties/taxes/cess & all other incidentals payable as per statute. Goods and Service Tax shall be paid extra as per statute.
- 13. **Correctness and Sufficiency of Rates Quoted in the Tender:** The bidder shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for work and the rates and prices stated in the schedule of works. The rates and price quoted shall cover all obligation of the bidder under the contract and all materials, labour etc. necessary for proper completion and maintenance of the work.

14. Amendment of Bidding Documents:

- (a) At any time prior to the deadline for submission of bids, WBSEDCL may, for any reason whether at his own initiative or in response to a clarification requested by a prospective bidder, modify the bidding documents by issuing amendments. Any such amendment shall be part of the bidding document.
- (b) Such amendment(s) will be published on the same website mentioned above. WBSEDCL will bear no responsibility or liability arising out of non-pursuance of the same in time or otherwise by the bidder. In order to afford prospective bidders reasonable time in which to take the amendment in to account in preparing their bids, WBSEDCL may, at its discretion, extend the deadline for submission of bids. Such amendments, clarification, etc. shall be binding on bidders and will be given due consideration by the bidders while they submit their bids and invariably enclose such documents as a part of the bids.

15. **Validity of Bid:**

- (a) Financial Bid shall preferably be opened within 30 (Thirty) days from the date of opening of Techno-commercial Bid.
- (b) The offer against the tender should remain valid for a minimum period of 180 days from the date of opening of Financial Bid.
- (c) Prior to the expiry of the original validity period WBSEDCL may request extension in the period of validity for a further suitable period without any change in terms & conditions of the offer.
- 16. **Earnest Money Deposit:** The bidder shall deposit the requisite earnest money through online or offline mode following payment options are available for payment of EMD, for the intending bidders.



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

- (a) Net-banking through Payment Gateway.
- (b) **RTGS/NEFT Payment**: On selection of RTGS/ NEFT as the payment mode, the e-Procurement portal will show a pre-filled challan having the details to process RTGS/NEFT transaction. The bidder will print the challan and use the prefilled information to make RTGS/NEFT payment using his bank account. Once the payment is made, the bidder will come back to the e-procurement portal to continue the bidding process after expiry of a reasonable time to enable the RTGS/NEFT process to be completed.
- (c) **Submission of EMD through BG:** For submission of EMD in the form of Bank Guarantee, the bidder will have to opt for EMD exemption in e-tender web portal and upload scanned copy of BG in the EMD exemption document upload section. Physical copy of BG shall be submitted at the Office of the Regional Manager, Malda within scheduled date and time.
- 17. **Process to Be Confidential:** After the opening of bids, information relating to the examination, clarification, evaluation and comparison of bids, and recommendations concerning the award of contract shall not be disclosed to bidders or other persons not officially concerned with such process.
- 18. **Right to Accept or Reject Any or All Offers:** WBSEDCL reserves the right to accept or reject any bid and to anal the bidding process and reject all bids at any time prior to award of contract without thereby incurring any liability to the affected bidder or bidders or any obligation to inform the affected bidder or bidders the reason for WBSEDCL's action. Effort by a bidder to influence WBSEDCL or other connected in the process of examination, clarification, evaluation and comparison of bids, and in decisions concerning the award of contract, may result in the rejection of his/their bid.
- 19. **Time Schedule:** The basic consideration and the essence of the contract shall be the strict adherence to the time schedule specified in the NIT.
- 20. **Evaluation and Comparison of Bids:** On examination of document submitted under different covers WBSEDCL will evaluate and compare the bid, determined to be substantially responsive at each step. Evaluation of bid will include and will take into account. Cost of construction/erection including taxes & duties etc. The owner shall evaluate and compare only the bids determined to be substantially responsive. The bids shall be evaluated on the basis of total price (Civil & Electrical Works Separately) for the entire scope of work covered under this bid document. Evaluated bid price of all bidders shall be compared among themselves to determine the lowest evaluated bid and as a result of this comparison, the lowest bid will be selected for award of contract. Conditional rebate, if any, offered by any bidder shall not be considered in Bid evaluation.

21. **Opening of Technical Proposal/Bid:**

- a) Technical proposals will be opened by authorized representatives of WBSEDCL from the web site stated using their Digital Signature Certificate.
- b) Intending bidders may remain present if they so desire.
- c) Cover (folder) statutory documents will be opened first and if found in order cover (Folder) for non-statutory documents will be opened. If there is any deficiency in the statutory documents the tender will be summarily rejected.
- d) Decrypted (transformed in to readable formats) documents of the non-statutory cover will be downloaded and handed over to the authorized representatives of WBSEDCL.
- e) Uploading of summary list of technically qualified bidders:



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

i. Pursuant to scrutiny & decision of the authorized representatives of WBSEDCL the summary list of eligible bidders& the serial number of works for which their proposal will be considered will be uploaded in the web portals.


ii. While evaluation the authorized representatives of WBSEDCL may summon any of the bidder& seek clarification/information or bidder(s) may be asked for producing original hard copy of any of the document already submitted & if these are not produced within the stipulated time frame, their proposals will be liable for rejection.

22. **Opening of Financial Bid:**

- by the Tender Inviting Authority (authorized representative of WBSEDCL) from the web portal stated above on the prescribed date.
- b) The encrypted copies will be decrypted and the rates will be read out to the bidders remaining present at that time.
- c) After opening of the financial proposal, the preliminary summary result containing inter-alia, name of the bidder and the rates quoted by them will be uploaded.
- d) The bids will be evaluated on the basis of technical and financial proposal for the entire scope of work covered under this bid document.
- e) The bidder whose offer has been accepted will be finalized after the evaluation procedure will be notified by the Tender Inviting Authority (authorized representative of WBSEDCL) through Letter of Intimation. The same will be made available/uploaded in the website https://wbtenders.gov.in.
- f) Decision of Tender Inviting Authority will be final and bound to every bidder.
- g) The selected bidder will be asked to produce the documents like Contract Agreement, Indemnity Bond, Performance Security and any other document on demand of WBSEDCL within a specified time-frame.
- h) WBSEDCL has the right to reject the tender if the bidder unable/disagree to produce the same.
- n) Conditional rebate, if any, offered by any bidder shall not be considered in Bid evaluation.

The Tender Accepting Authority may ask any of the bidders to submit analysis to justify the rate quoted by that bidder. If the successful bidder will not enter into Contract Agreement and/or submit the performance security/contract performance and/or Indemnity Bond within stipulated time as mentioned in the Letter of Intimation, his EMD will be forfeited and the job may subject to be cancelled.

- **20.** Taxes, Duties and Other Levies: The contractor shall be solely responsible for the taxes that may be levied on the contractor's persons or on earnings of any office employee and shall hold the purchaser indemnified and harmless against any claims that may be made against the purchaser. The purchaser does not take any responsibility what- so-ever regarding taxes under Indian Income Tax Act, for the contractor or his personnel. If it is obligatory under the provisions of Indian Income Tax Act, deduction of Income Tax at source shall be made by the purchaser. All other taxes/duties/levies/cess payable (excluding Good and Services tax) by the bidder shall be included in the bid price and no claim on this behalf will be entertained by the owner.
- **21. Laws Governing Contract:** The contract shall be construed according to acts/laws in force in the country and shall be under the jurisdiction of Calcutta High Court.



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

- **22. Language and Measures:** All documents pertain to the contract including specifications, schedule, notice, correspondences, operating and maintenance instructions, drawings or any other writings be written in English language. The metric system of measurement shall be used exclusively in this contract.
- 23. Corrupt or Fraudulent Practice: WBSEDCL expects that bidders/contractors observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, the owner defines for the purpose of this provision, the terms set forth below as follows:
- "Corrupt practice" means the offering giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution, and
- "Fraudulent Practice" means misrepresentation of facts in order to influence a procurement process of the execution of a contract to the detriment of the owner, and includes collusive practice among bidders (Prior to or after bid submission) designed to establish bid prices at artificial no-competitive levels and to deprive the owner of the benefits of free and open competition Will reject a proposal for award if the owner determines that the bidder recommended for award has engaged in corrupt or fraudulent practice in competing for the contract in question Will declare a Firm ineligible either indefinitely or for a stated period of time if owner any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing the contract.
- **24. Insurance:** The successful bidder on awarding of contract shall arrange, secure and maintain all insurance as may be pertinent to the work and obligatory in terms of law to protect the interests of WBSEDCL against all perils. The form & the limit of such insurance together with underwriting in each case shall be acceptable to WBSEDCL. However, irrespective of such acceptance the responsibility to maintain adequate insurance coverage at all times during the period of contract shall be bidder's alone.
- 25. Correctness and Sufficiency of Rates Quoted in the Tender: The bidder shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for work and the rates and prices stated in the schedule of works. The rates and price quoted shall cover all obligation of the bidder under the contract and all materials, labour etc. necessary for proper completion and maintenance of the work.
- **26. Penalty for Suppression/Distortion of Facts:** If any Bidder fails to produce the original hard copies of the documents (especially Completion Certificates and audited balance sheets), or any other documents on demand of the Tender Committee within a specified time frame or if any deviation is detected in the hard copies from the uploaded soft copies or if there is any suppression, the tender committee will take action as deem fit against such defaulting Bidder. The Employer reserves the right to accept or reject any Bid and to cancel the Bidding processes and reject all Bids at any time the prior to the award of Contract without thereby incurring any liability to the affected Bidder or Bidders or any obligation to inform the affected Bidder or Bidders of the ground for Employer' section.
- **27. Award of Contract:** The Bidder who's Bid would be accepted will be notified by the authorized official through acceptance letter/Letter of award. The notification of award will constitute the formation of the Contract. The Agreement and Indemnity Bond as per enclosed format in G.C.C. will incorporate all agreements between the Tender Accepting Authority and the successful bidder. All the tender documents



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

including N.I.T. & B.O.Q. will be the part of the contract documents. General Condition of Contract for Civil and Electrical works are post bidding documents and is totally of agreement with lowest bidder, don't consider it as prequalification criteria.

- **28.** Litigation/Arbitration against WBSEDCL: The bidder should submit the declaration in prescribed format (Form-XI) in their letterhead regarding no legal litigation against WBSEDCL is pending in any court/forum against/ by the bidder or it's sister concern/Director/Partner/Proprietor. If any type of legal litigation against WBSEDCL is pending in any court/forum against/ by the bidder or it's sister concern/Director/Partner/Proprietor, then purchaser reserves the right to reject their bid/termination of the contract.
- **29. Holiday Listing**: Every Bidder shall at the time of submission of bid have to submit a declaration in prescribed format (Form IX) as attached, in their letterhead that the bidder has not been placed on holiday list/blacklisted by WBSEDCL /Statutory/Regulatory/Government Authorities/State Electricity Utility/PSU. If the bidder is a proprietary concern, the proprietor shall also give a declaration in prescribed format (Form X) as attached, in their letterhead at the time of submission of bids that none of the other concerns of which he is a proprietor or Managing Partner, has been placed in Holiday list /Blacklist by WBSEDCL /Statutory/Regulatory/Government Authorities/State Electricity Utility/PSU. In case the declaration of a party indicates that either the company or a Proprietorship concern of the same Proprietor or a Partnership firm in which the Proprietor is also a Managing partner has been placed on Holiday/Blacklist by WBSEDCL/Statutory/Regulatory/Government Authorities/State Electricity Utility/PSU, the party shall put on holiday list.
- **30.** Contract Agreement: The agreement as per enclosed format specified in 'annexure -A' of this tender will incorporate all agreements between the tender accepting authority and the successful bidder. All the tender documents including NIeT and BOQ will be part of the agreement. After acceptance of Letter of Award, the successful bidder shall have to submit requisite copies of contract documents stated as per 'Clause No.-8 of General Conditions of Contract (GCC)'.
- **31. Indemnity Bond:** The contractor (successful bidder) shall have to produce Indemnity Bond as per 'annexure -B' within the stipulated time as mentioned in the Letter of Award (LOA) to 'The Regional Manager, Regional Office, WBSEDCL'.
- **32.** Creation of Vendor Id Through WBSEDCL Web Portal: All Participating bidder(s) shall have to mandatorily create vendor Id through WBSEDCL Web Portal Vendor Corner, if not created earlier.

West Bengal State Electricity Distribution Company Ltd. (A Govt. of West Bengal Enterprise) MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

Form-I - CERTIFICATE REGARDING SUMMARY STATEMENT OF YEARLY TURNOVER

		Financial	
Sl.No.	Financial Year	Turnover Rounded Upto Two Digit After Decimal	Remarks
1.	2023-24		
2.	2022-23		
3.	2021-22		
	Total		

SIGNATURE OF THE TENDERER WITH OFFICE SEAL



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101. Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Malda, WB- 732101. E-mail: <u>rm.malda@wbsedcl.in</u>

Form-II - EVIDENCE OF ACCESS TO OR AVAILABILITY OF CREDIT FACILITIES

(To be given by banker of bidder) BANK CERTIFICATE

are sı speci	ubmitting th	neir Bid tole Ref. No		(Full Name and Address)Whoagainst their tender is our customer for
based	l limits inc		and other credit facilities with	followingfundbasedand non-fund- us against which the extent of
	Sl.No.	Type of Facility	Sanctioned limit as on date	Utilization as on date
This	letter is issu	ned at the request of M/s.		
Sd/-				
Name	e of Bank			
Namo	e of authori	zed Signatory		
Desig	gnation			
Addr	ess			

SEAL OF THE BANK

We/t Bengal /tate Electricity Di/tribution Company Ltd. (A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Form- III - STATEMENT OF SIMILAR TYPE OF WORKS (CIVIL & ELECTRICAL)EXECUTED DURING LAST 07 (SEVEN) YEARS.

SI. No.	Name of the work executed	Nature of the project to which the work is related	Order No. and date(s)	Name of Owner/ order issuing authority	Financial year	Executed value (Rs.)	Date of commencement, scheduled completion &actual completion	Whether Completion/ Payment Certificate(s) submitted (Y/N)

Remarks, if any:	
	SIGNATURE OF THE TENDERER WITH OFFICE SEAL

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: <u>rm.malda@wbsedcl.in</u>

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

FORM -IX

(On the Bidder's Letterhead)

Declaration of not being blacklisted/Debarred/Put on holiday listing

Certified that our Company, M/ss not blacklisted/ debarred/ suspended or put on
holiday list by any Statutory/Regulatory/Government Authorities/ State Electricity Utility/ PSU in India.
It is certified that the information furnished above is true to the best of my knowledge and belief.
Bidder's Name:
Signature of the Tenderer:
Designation:
Seal of the Company:
Date:

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101. Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Malda, WB- 732101. E-mail: <u>rm.malda@wbsedcl.in</u>

FORM-X

(On the Bidder's Letterhead)

<u>Self-declaration by Proprietor of the Bidding Company for not being blacklisted/ Debarred/</u> Put on holiday listing

I hereby confirm and declare that, none of the other concerns of which I am a proprietor /Managing Partner are blacklisted/ debarred/ suspended or put on holiday list by any Statutory/ Regulatory/ Government Authorities/ State Electricity Utility/ PSU in India.

It is certified that the information furnished above is true to the best of my knowledge and belief.

Signature of the Proprietor.
Name:
Designation:
Seal of the Company:
Date:

Cianatura of the Duamietem

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: <u>rm.malda@wbsedcl.in</u>

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

FORM -XI

(On the Bidder's Letterhead)

Declaration regarding no litigation against WBSEDCL

We hereby declare that no legal litigation/arbitration is pending/ongoing against WBSEDCL in any court/Forum against/by the bidder or its sister concern/Director/Partner/Proprietor.

If it is found at any stage of tendering, our offer will be rejected and I/We don't have any objection on the same

Bidder's Name:
Signature of the Tenderer:
Designation:
Seal of the Company:

Date:



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

FORM-XII

(On Rs.100.00 Non-Judicial Notarized Stamp)

PROFORMA FOR UNDERTAKING TO BE SUBMITTED BY THEBIDDER

(For genuineness of the information furnished on-line and authenticity of the Documents produced before Tender Committee for verification in support of his eligibility)

Ι,	,Partner/Legal Attorney/Accredited representative of M/S
	_, solemnly declare that:
1.	We are submitting Tender for the Work against Tender Notice Nodt
2. the Cor	None of the Partners of our firm is relative of employee of (Name of mpany).
3. formatio	All information furnished by us in respect of fulfillment of eligibility criteria and qualification in on of this tender is complete, correct and true.
4.	All documents/credentials submitted along with this Tender are genuine, authentic, true and valid.
	If any information and document submitted is found to be false/incorrect any time, department may my Tender and action as deemed fit may be taken against us, including termination of the contract, re of all dues including Earnest Money and banning/delisting of our firm and all partners of the firm
	(Signature of Authorized Signatory)
	Name:
	Designation:
	Seal:

We/t Bengal /tate Electricity Di/tribution Company Ltd. (A Govt. of West Bengal Enterprise) MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

FORM-XIII

Format of Letter of Bid

LETTER HEAD OF BIDDER (AS ENROLLED ONLINE ON e-tendering PORTAL OF NIC)

To The Tender Com	mittee
Sub: Letter of Bi	d for the work
Ref: 1. NIT No	dated
2. Tender Id	No
Dear Sir,	
	to execute the work as per our offered bill of quantity in accordance with the NIT document as available in the website. The details of the EMD being submitted by shed on-line.
This Bid contract between	and your subsequent Letter of Acceptance/Work Order shall constitute a binding us.
We hereby unconditionally.	y confirm our acceptance of all the terms and conditions of the NIT document
	(Signature of Authorized Signatory)
	Name:
	Designation:
	Seal:



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091.

Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Postal address of the Bidder

Company of the state of the sta

We/t Bengal/tate Electricity Di/tribution Company Ltd.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

Malda, WB- 732101. E-mail: <u>rm.malda@wbsedcl.in</u>

(Official Address)

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

ANNEXURE-II

PROFORMA OF BANK GUARANTEE FOR BID GUARANTEE/SECURITY The non-Judicial stamp paper of Rs 100.00 should be in the name of issuing bank	
Ref	Bank Guarantee No
Date To The	
West Bengal	
Dear Sirs,	
its Registered/Head	favour have agreed to accept an irrevocable andvalid upto on behalf of Bidder in lieu of the ondition precedent for participation in the Said Bid. s) having our Head Office atGuarantee and the Electricity Distribution Company Ltd., the Amount
This Guarantee shall be irrevocable including	
(Signature)	(Signature)
(Name) (Name)	(Signature)

* This date shall be 30 (thirty) days after the last date for which the bid is valid.

(Official Address)



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

GENERAL CONDITIONS OF CONTRACT AND SPECIFICATION FOR CIVIL WORK



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

GENERAL CONDITIONS OF CONTRACT AND SPECIFICATION FOR CIVILWORKS

1. Definition of Terms:

In writing these General Conditions of Contract, Specification and Bill of quantity/bidding schedule (schedule of work) the following words shall have normally the meanings here-in- after indicated unless there is something in the subject matter of content inconsistent with such construction.

The **Company/purchaser/Owner/Department** shall mean the WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LTD, having its Office at Vidyut Bhavan, Block-DJ, Sector-II, Kolkata-700091

The **Engineer-in-Charge/Controlling Officer** shall mean the Engineer designated by the Company for the purpose of this contract.

Company's representative shall mean any person or persons of consulting firm appointed and remunerated by the Company to supervise, inspect, test and examine workmanship and materials of the work under this scope.

The **Contractor** shall mean the Bidder who will be awarded with the contract by the Company and shall include the contractor's executor's administrators, successors and permitted assignees.

Equipment/materials shall mean and include all type of construction equipment & materials etc. required for true and satisfactory completion of the work under this contract.

Workmanship shall mean the method/manner in which the jobs of the different items, whether included in the schedule or not but are required for true & satisfactory completion of the work under this contract, are executed.

General conditions shall mean all the clauses of General conditions of the proposed contract stated hereinafter. The specification shall mean the specification annexed to or issued with the General Conditions and shall include the schedule and drawings attached thereto.

The terms **Services** shall mean all works to be undertaken by the contractor as laid down under the head "scope of contract" or elsewhere in the specification enclosed. When the words "approved", "subject to Approval", "As directed", "Accepted", "Permitted" etc. are used, the approval, judgment, direction etc. are understood to be a function of Company.

Month shall mean calendar month.

"Writing" shall include any manuscript, type written, printed or other statement reproduced in any visible form.

The work 'Site' shall mean the site of proposed work as detailed in the specification or any other place where the work is to be executed under the contract.

'Date of Contract' shall mean the date on which notification of award of contract/letter of award/telex award has been issued.

'Zero Date' will be reckoned as the date of date of handing over of site.



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

2. Scope of Work:

Scope of work includes "Construction of security room, car parking shed, surrounding area development with paver block along with some gardening, installation of main gate along with gate pillar, painting of boundary wall including Electrical wiring of the building at Chanchal Administrative Building under Chanchal Division". The proposed contract comprises of construction, repair and maintenance of the work during the contract period including defect liability period, as required. It includes provision of all labour, material, constructional plant, temporary work and everything whether temporary or permanent nature required for such construction, completion and maintenance so far as the necessity of providing the same is specified in or responsible to be inferred from the contract. The different items of work have been elaborated in the schedule of work.

3. Submission of Tender:

Please refer to sl. no 6 of Instruction to Bidders

4. Performance Bond/Security Deposit:

In respect of successful Bidder, the Earnest Money deposit on acceptance of Tender shall be converted as a part of the Security Deposit. The successful bidder shall have to submit balance Earnest money, if required, to make the initial Security money amounting to 2% of the contract price after placement of Letter of acceptance/Letter of award within specified period. Balance of Security Deposit equivalent to 8% (Eight percent) of contract amount shall be realized by recovering from the progressive bill @8% (Eight percent) of the amount of each successive bill. In all cases the amount of recovery of the Final Bill will be so adjusted as to make the total amount of Security Deposit equivalent to 10% (Ten percent) to the value of work so executed.

In case of EMD in the form of Bank Guarantee is opted, the successful bidder shall have to furnish a Performance Bank Guarantee to the tune of 10% (Ten Percent) of the contract amount within 14 days from the receipt of or placement of LOA, whichever is later, to guarantee the faithful performance and security of the contract in accordance with all the conditions and terms stipulated herein and the relevant format attached. The successful bidder may withdraw the EMD (@ 2 % of Tender value) submitted in the form of Bank Guarantee after furnishing the Performance Bank Guarantee @ 10% (Ten Percent) of the contract amount. In such case no deduction from successive bills will be made to realize the Security Deposit. Performance Bond will also have the guarantee for successful and satisfactory performance of materials supplied under the contract till the expiry of the guarantee period. Earnest money in the form of Bank Guarantee of the unsuccessful bidders may be realized by the respective bidders after finalization/placement of order.

Bids in range of -20% to -80% of the estimated rate shall furnish an Additional Performance Security in the format given in the Annexure which shall be equal to 10% of the tendered amount before placement of Award of Contract.

5. Refund of Security Deposit:



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091.

Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Refund of Security deposit shall be subject to Company's right to deduct/appropriate its dues against the contractor or under this contract or any other contract. The performance Bond/Security Deposit for all type of Bids shall be released only after satisfactory expiry of the guarantee period and certified as such by the controlling officer of the work upon written request by the contractor under following conditions:

In case of building works or other similar nature of works the defect liability period shall be considered six month or expiry of one full monsoon period, i.e. June to September whichever is later and any defects such as leakages in roof, effloresces in walls, dampness, defects in drainage etc. should be rectified to the satisfaction of the engineer.

All types of Manufacturer's guarantee/warranty wherever applicable are to be issued/revalidated in the name of owner by the contractual agency. In case of building works or similar nature of works the defect/ liability period shall be considered six months or expiry of one full monsoon period i.e. from June to September whichever is later.

6. Refund of Earnest Money:

For unsuccessful bidders, EMD amount submitted against the tender shall be refunded automatically, through an automated process, by NIC portal on receipt of updated status of any bid.

For successful bid(s), EMD will be refunded from WBSEDCL authority after completion of tendering process and following due procedures.

The bank account used for payment of EMD by the bidders shall be maintained operative until the completion of tendering process. All refunds will be made mandatorily to the Bank A/c from which the payment of EMD has been initiated.

For any queries related to payments and refunds, bidders will have to communicate with ICICI Customer Support, viz. 033-4O267512/l3 since payment gateway facility used by E-tender portal is maintained by ICICI.

Successful bidder(s) shall have to mandatorily create vendor id through WBSEDCL Web Portal Vendor Corner if not created earlier.

Forfeiture of Earnest money/Bid Guarantee:

Earnest money/Bid guarantee shall be forfeited in case of following:

- a) If during the period of validity, the bidder withdraws/modifies its bid as a whole or in part.
- b) If the bidder deviates from any clarification/confirmation given by him subsequent to submission of his bid.
- c) In case of successful bidder, if the Bidder fails:
 - i. To accept LOI/Order unconditionally and sign contract
 - ii. To furnish the contract performance bond / Additional Performance Security in the form of Bank Guarantee wherever applicable.

7. Defect Liability Period:



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

The term 'defect liability period' shall mean the period of **Six** (6) months or one full monsoon, whichever is later, from the Date of completion of the work. If any defect is found within the defect liability period the contractor shallbeliabletorectify/replacethematerialsattheirowncostandresponsibility.

In case any defect of work is detected by the controlling officer within the period initial defect liability period, the defect liability period is liable to extend beyond the stipulated time.

Defects/rectification work so notified shall have to be attended and completed satisfactorily within the specified date or as deemed fit by the Controlling Officer. For faithful & due fulfillment of all obligations, this defect liability period shall be covered by Security Deposit submitted by the contractor detailed in clause5.0.

After completion of defect liability period, and on completion of satisfactory rectification of defects, if any reported within the defect liability period, and on receipt of the application from the contractor the controlling Officer of the work will recommend release of security deposit.

8. Manner of Execution:

The successful bidder has to submit acceptance of the LOI/order within **10(ten)** days from the date of issue of the Letter of Intent/order. The successful bidder shall be required to execute an Agreement on a non-judicial tamp paper of Rs100/- with the company with all related documents for satisfactory execution of the work. The agreement shall be signed on a date and time to be mutually agreed upon in the office of the controlling officer of the work and the same has to be signed by both the parties within 30 days from date of acceptance of the order. Power of attorney of the authorized representative of the contractor who will sign the contract agreement on behalf of the contractor is to be submitted before signing of the agreement. The agreement shall be signed in original and five photo copies.

The original agreement shall be retained by the Company and a copy will be handed over to the Contractor.

9. General Requirement: The contractor shall execute, complete and maintain the work as per direction of the Controlling Officer/Engineer-in-Charge of the work or his representative.

10. Contractor to submit programme:

Within 14 (fourteen) days from the date of issue of letter of intent/order, the contractor shall submit a programme showing the order, procedure and method in which he proposes to carry the work.

11. Contractor's staff at site:

The Contractor shall provide at site his authorized representative duly approved by the controlling officer (approval may be withdrawn for a person, if necessary). The contractor and/ or his authorized representative is to be constantly on the work and shall give whole time supervision of the same. Such authorized agent or representative shall receive (on behalf of the contractor) direction and instructions from the Controlling Officer/ Engineer-in-charge or his representative.

12. Removal of persons employed at site:

The Controlling Officer/ Engineer-in- Charge shall be at liberty to ask the contractor to remove from the site any person, employed by the contractor in the execution of work, who in the opinion of the Controlling Officer/ Engineer-in-Charge misconducts himself or is incompetent or negligent in the proper performance of his duties and such persons shall not be again employed upon the work without the permission of the Controlling Officer/Engineer-in-Charge.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

13. Setting-out:

The contractor shall be responsible for the true and proper setting out of the work and for the correctness of the position, levels, dimensions and alignments of all parts of the work. If any time during the progress of the work any error shall appear or arise in the positions, levels, dimensions or alignments of any part of the work, the contractor on being asked to rectify by the Controlling Officer/ Engineer-in-Charge or his representative shall at his own expense rectify such error to the satisfaction of the Controlling Officer/ Engineer-in-charge.

14. Protection of work:

The Contractor shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching when and where necessary if required by the company or by any competent authority for the protection of the work or for the safety and convenience of the public or others.

15. Care of works:

From the commencement to the completion of the works, the contractor shall take full responsibility for the care of permanent works, therefore and of all temporary works and in case of any damage, loss, or injury to works or to any part thereof or any temporary works due to any cause whatsoever shall at his own cost repair and make good the same, so that at completion the works shall be in good order and condition and in conformity in every respect with the requirements of the contract. The contractor shall take every practicable precaution not to damage or to cause injury to any adjoining or other properties or to any persons. However even if any damage or injury occurs, the contractor shall be responsible in meeting the necessary claims and demands as may be required.

16. Workmen's Compensation for accident or injury to any workman:

The Company shall not be liable for damages or compensation payable as per provision of law in respect or consequence of any accident or injury to any workmen or other person in the employment of the contractor. The contractor shall have to pay all claims, demands, last costs, charges and expenses whatsoever in respect thereof or in relation thereto. Insurance policy covering provisions for workmen's compensation for all the workmen to be engaged by the contractor is to be made by him.

17. Facilities for other Contractors:

The Contractor shall afford all reasonable facilities for any other contractor employed by the company in execution on or near the site of any work not included in the contract.

18. Clearing site on completion: On Completion of the work the Contractor shall clear away and remove from the site all constructional plant, surplus materials, rubbish and temporary work of every kind and leave the whole of the site and work clean and in good and tidy condition to the satisfaction of the Controlling Officer/ Engineer-in-charge.

19. Change of Quantity:

The quantity mentioned in the schedule of work is provisional. The company reserves the right to vary the quantities as may be necessary but such variation shall be limited to+25%(plus twenty five percent) of the contract price. Payment shall be made as per execution.

20. Goods & Services Tax(GST):



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

Goods and Services Tax shall be paid extra as per prevailing statute.

21. Labour License:

Contractor will have to obtain Labour License in respect of the above work as per Contract Labour (Regulation & Abolition) Act, 1970 as early as possible.

22. Compliance of Labour Laws:

The contractor shall comply all statutory labour laws to protect the laborers engaged by them. In this connection the contractor will be required to execute an indemnity bond (as per specimen enclosed as Annexure-B)after placement of letter of intent/order.

23. Night and Holiday Work: If any work of permanent nature is to be carried out in three shifts and/or in Sundays & Holidays, prior written permission of the Controlling Officer shall have to be obtained.

24. Deductions of Provident Fund and remittance thereof in respect of contract labourers:

In respect of casual workers or workers engaged for any job for a very short duration or sporadic nature having no employer-employee relationship (for example Soil testing, repair of transformer etc. done by outer agency) and engaged in works which are neither preparatory, nor incidental, nor any way connected with the main operation of the establishment, deduction of provident fund and remittance thereof in respect of the contract labourers will not be applicable. However, it is further clarified that no mechanical approach should be adopted in deciding the applicability of the Act and each case should be considered on its own merits.

25. Variation, Omission, Addition & Alteration:

The Contractor shall not modify the work except under direction in writing by the Company. The quantities provided in the Schedule of work are provisional only, which may vary upto any extent or may be deleted altogether. The quoted rate of each item shall remain firm till completion of contract. The Company reserves the right to alter, amend, and omit or other vary the quantities as may be necessary but such variation will be limited to +25% (plus twenty-five percent) of the contract price. Payment shall be made as per actual execution.

26. Paying Authority:


The Manager (F&A), Regional Office, Malda, WBSEDCL shall be the paying authority.

27. Supplementary Works:

Whenever supplementary work becomes unavoidable for completion of the work in all respect, the Contractor shall bring the matter to the notice of the Controlling Officer and submit their proposal. However, the controlling officers shall have the right to advise the contractor to proceed with such item (s) of work. Rates for supplementary item shall be arrived at as given hereunder:

The rates of all supplementary items shall be decided on pro-rata basis from the existing items in the contract. When above clause no 19 shall not be applicable the rates shall be taken from P.W.D (WB) schedule of rates for building works, sanitary & plumbing works &PWD (WB)(Roads) schedule Prevailing at the time of submission of bids plus/minus the contractual rate of quotation.

When clause no 19 above shall not be applicable, the rates should be analyzed, to the mutual acceptance from present market rates of different elements involved in the item, against documentary evidence, with contractor's profit as 10% and 1% cess towards BOCWWC Act,1996. In that case contractual rate of quotation will not be applicable.



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

Controlling Officer's decision regarding finalization of rate of non-scheduled item(s) shall be final and binding upon the contractors.

28. Measurement and Terms of Payment:

All items of work carried out by the contractor in accordance with the provision of the contract having a financial value shall be entered in the measurement book/ log book etc. as prescribed by the company so that a complete record is obtained of all works performed underthecontractandthevalueofworkcanbeascertainedanddeterminedtherefrom.

Measurement shall be taken jointly by the supervisory officer or his authorized representative and by the contractor or his authorized representative. Every measurement thus taken shall be signed and dated by both the parties.

In the event of failure on the part of the contractor to attend or send his authorized representative after receiving the information to countersign or record objection within a week from the date of measurement, the measurement taken by the Engineer-in- charge/controlling officer or his authorized representative shall be taken to be correct measurement of the work done.

Progressive R/A bills against the prayer of the contractor, for an amount of minimum 20% of the ordered value or as deemed justified by the controlling officer shall be released against certification by the controlling officer after deducting the amount already paid or other amounts as may be deductible. The bills shall be released within 30(thirty) days of its submission if all formalities as per terms of the contract is maintained. The final bill shall be released on completion of the work in all respect and fulfillment of all contractual obligations by the contractor.

The company reserves the right to recover/ enforce recovery of any overpayments detected after payment as a result of post-payment audit or technical examination or by any other means, notwithstanding the fact that the amount of disputed item, if any, of the contractor exceeds the amount of such overpayments and irrespective of the fact whether such disputed claims of the contractor are subject matter of arbitration or not. The amount of such overpayment may be recovered from subsequent bill, under the contract, failing that from contractor's claim under any other contract with the company or from contractor's security deposit or from the amount retained or the contractor shall pay the pay the overpayment on demand. All payments shall be made against submission of GST prescribed invoice incorporating GSTI Number, SAC code and other necessary particulars.

29. Completion of Contract:

All works under the contract must be completed by period of completion mentioned in NIT while portions of work as per programme settled in consultation with the controlling officer shall be completed by the date stipulated in the programme. It is to be noted that time is the essence of the contract and any default on the part of the contractor to complete the work within the stipulated date/dates aforesaid or within the time as may be extended in writing by the controlling officer subject to the payment of liquidated damages, the company shall have the right ,without prejudice to any other clauses, to terminate the contract forthwith and to take possession of balance work/ materials and have the same allotted to any other agency and the contractor shall be liable to compensate the loss that may be occasioned to the Company on that account. Any letter in writing by The Controlling Officer shall be treated as conclusive on behalf of the Company.

30. Defective Material:



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

If in the opinion of the Engineer-in-Charge/Controlling Officer, any of the materials brought to the site for use are not of the quality or kind specified in the contract and/or are unfit for work, he shall be at liberty to order the removal of the said materials and the contractor shall remove the same within 24(twenty four)hours after notice has been given to him, and if he fails to remove them within the time the Engineer may cause them to be removed anywhere at the risk of the contractor and any cost incurred in so doing shall be deducted from the dues to the contractor under the contract.

31. Drawings

The work shall be carried out in accordance with the instruction and to the satisfaction of the Engineer-in charge in accordance with the signed drawings, the specifications and schedule of quantities and also as per any further drawings which may be supplied, all instruction which may be given by the Engineer-in-charge/Controlling Officer from time to time.

32. Material and Workmanship:

All the work shall be executed with the materials as specified and with best workmanship and/or in the best manner to the satisfaction of the Engineer-in-Charge/Controlling Officer.

33. Extension of Time:

If the work is suspended due to reasons beyond the control of the contractor, the contractor shall immediately give notice in writing within 7(seven) days to the controlling officer for each occasion. On receipt of such notice, the controlling officer may verify the matter and agree to extend the completion period as may be reasonable but without prejudice to other terms and conditions of the contract as the case may be if the reasons behind the suspension of work are found to be justified.

34. Liquidated Damages (LD):

If the contractor fails to complete the work successfully within the time specified in the contractor any extension thereof, the company shall recover from the contractor as liquidated damages a sum of half percent (0.5%) of the contract value of works for each calendar week of delay or part thereof of delay subjected to Force Majeure. The total recovery against liquidated damage shall not exceed ten percent(10%) of the contract value of the work.

An extension of time without imposition of liquidated damage, may be granted for delay in execution of work provided there is no fault whatsoever on the part of the contractor. Such extension may only be granted on the basis of application to be submitted by the contractor—who has to establish that the extension of time required by him was not due to his fault.

35. Company's Right to Terminate the Contract:

If the contractor neglects or fail to proceed with the work proportionate to the scheduled time of completion or fails to complete the work within scheduled time of completion or within extended time approved by the company, the company shall have right to terminate the order, Letter of intent, after giving notice in writing to the contractor. If the contractor fails, after 14(fourteen) days of such notice, to proceed with the work in the manner notified, the company shall terminate the contract and call the contractor to take joint measurement along with the Engineer for finished portion of work. If the Contractor does not appear for a joint measurement, ex-party measurement taken by the company will be taken as final.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

In that case, the company shall take possession of the work site and may engage other agency to complete the work. Extra cost, if incurred to get the unfinished work done through other agency, will be realized from him, from his pending bills and security deposit. If the contract is terminated as above, the contractor shall have no claim for compensation against the company for any loss or deterioration of any materials that he may have collected or engaged or entered into on account of the work.

36. Quality of Work/Material and Mode of Measurement:

As regards to the specification of materials, execution of work and the mode of measurement relevant stipulation of P.W.D schedule of rates (applicable at site of work) in this respect shall be applicable. The Contractor shall arrange and provide all necessary facilities along with necessary man power for inspection, testing and measurements at his own cost.

37. Departmental Materials:

Departmental materials shall not be issued to the contractor for the work except under special circumstances.

38. Deduction of Taxes and Cess for BOCWWC Act, 1996:

If it is obligatory under the provision of Income tax Act 1961 to deduct tax at source then the same will be deducted from the bills as applicable. The contractor is required to follow the Building and other Construction Worker's welfare Act, 1996.Registration of his establishment under section-7 of the Building and other Construction Worker's (Regulation and condition of service) Act, 1996 is to be made after the contract is awarded. 1% cess towards BOCWWC Act, 1996, will be deducted from its total amount of each bill. For this deductions certificate will be issued as per rules.

39. Force Majeure:

The Contractor shall not be liable to pay any liquidated damage for delay/failure to perform the contract for reasons of force majeure such as acts of God, acts of the public enemy, acts of Governments, fire, flood, epidemics, quarantine restriction, strikes, freight embargos and provided that the contractor shall within 10(ten) days from the beginning of such delay notify the Company in writing of the cause of delay. The Company shall verify the facts and grant such extension as found to be justified without imposing liquidated damage. The department shall not be responsible or liable to pay any compensation for any interruption in your work at the site due to strike, lockout, riot earthquake, flood, cyclone or civil commotion or any other force of accident due to any reason beyond control. The department shall not be held responsible to or liable to pay for any interruption in your work at the site arising out of resistance from the local public due to any resistance towards work.

40. Sub-Letting of Contract:

The contractor shall not, without the written consent of the Company, assign or sublet his contract or any part thereof, other than for raw materials, or for any part of the work provided that any such consent shall not relieve the contractor form any obligation, duty or responsibility under the contract. In the event of sub-letting of contract or any part thereof is permitted, the fact that such permission has been accorded shall not establish any contractual relationship between the approved Sub-vendor and WBSEDCL of any of his liabilities and obligations under the contract.

41. Engineer's Decision:

Controlling Officer's decision is final in respect of all matters which are left to the decision of the Controlling Officer including the granting or with-holding of certificates. If, in the opinion of the



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

contractor, a decision made by the Controlling Officer is not in accordance with the meaning and intent of the contract, the contractor may file with the Controlling Officer, within 7 (seven) days after receipt of the decision, a written objection to the decision. Failure to file an objection within the allotted time will be considered as an acceptance of the Controlling Officer's decision and the decision shall become final and binding.

42. Liability of Accidents and Damage:

The Contractor shall be responsible for the loss, damage or depreciation of the Company's materials while in their custody and until the same is taken over by the Company. Until the completed work is taken over by the Company the contractor shall also be liable for and shall indemnify the Company in respect of all injury to person or damage to properly resulting from the negligence of the contractor or his workmen or sub-contractor or from defective workmanship etc.

43. Language and Measurement:

All documents pertaining to the contract including specifications, schedule notices, correspondences, operating and maintenance instruction, drawings or any other writings be written shall in English language. The metric system measurement shall be used exclusively in this contract.

44. Settlement of Disputes:

All disputes concerning question of act arising under the contract shall be decided by the owner/company on receipt of written appeal by the contractor.

Any dispute or differences arising out of or in connection with this contract shall to the extent possible be settled amicably and where settlement cannot be reached then such disputes shall be subject to settlement under the jurisdiction of Calcutta High Court.

45. Completion of Work:

Completion of the work means completion of the work in totality and acceptance/takeover of the same by the Company. Partial or phase wise completion will have no bearing towards consideration of guarantee/defect liability period.

46. Controlling Officer:

The **Regional Manager**, **Malda Regional Office**, **WBSEDCL** shall be the Controlling Officer.

47. Technical Controlling Officer:

For Civil Works the **Assistant Engineer (Civil), Malda Regional Office, WBSEDCL** shall be the Technical-Controlling Officer and for Electrical Works the **Divisional Manager, Chanchal Division, WBSEDCL** shall be the Technical-Controlling Officer.

48. Supervising Officer:

The Junior Engineer (Civil), Malda Regional Office, WBSEDCL shall be the Supervising Officer & The Station Manager, Chanchal CCC, WBSEDCL for electrical works shall be the Supervising Officer respectively.

49. Nodal Officer:



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

The Manager (HR &A), Regional Office, Malda, WBSEDCL shall be the Nodal Officer.

50. Idle Labour/Machinery:

Whatever the reasons may be no claim for idle labour and machinery, additional establishment cost, hire and labor charges of tools & plants would be entertained by the Company, under any circumstances.

51. Safety Rules:

The bidder shall also provide necessary fencing and lights to protect the public from accident. Fire extinguishers shall be kept by the bidder at the side of works where there is risk of fire hazard. Adequate washing facilities shall be provided near the place of work. When the work is done near any place where there is risk of drowning, all necessary equipment shall be provided and kept ready for use and all necessary steps taken for prompt rescue of any person in danger and adequate provisions shall be made for prompt first aid treatment of all injuries likely to be sustained during the course of work. These safety provisions shall be brought to the notice of all concerned by displaying on a notice board at a prominent place at the work spot. The persons responsible for compliance of code shall be named by the bidder.

To ensure effective enforcement of the rules & regulations relating to safety precautions, the arrangement made by the bidder shall be open to inspection by the employer and WBSEDCL.

Not withstanding the above clauses there is nothing in those to exempt the bidder from the operations of any other Act or Rule in force in the Republic of India. All storage, handling & use of flammable liquids shall be under the supervision of qualified persons. First aid arrangements with the degree of hazard and with no. of workers employed shall be maintained in a readily accessible place throughout the whole of working hours.

52. Reporting of Accident:

All accidents, major or minor, must be reported immediately to WBSEDCL and the contractor will provide first aid to the injured person immediately. The injured person shall report to the First Aid Station along with the 'Injured on work' form as per appropriate proforma duly filled in quintuplicate and submit to the Medical Officer of the First Aid Station.

53. Serious Injuries:

In case of serious injuries, the following procedure shall be adopted by the contractor to provide first aid at his own First Aid Station. To take the injured person to the hospital along with the 'Injured on work' form duly filled in to report the accident to WBSEDCL.

54. Fatal Accident:

Fatal accidents must be reported immediately to WBSEDCL as well as to the Police.

55. Penalty:

Failure to observe the Safety Rules will make the contractor liable to penalty by way of suspension of work and termination of contract. Adequate arrangement for proper lighting & guarding shall be made at the work site.

56. Equipment & Machineries:

For timely completion of the work the bidder/contractor must have to deploy all necessary equipment, tools & tackles and machineries e.g. J.C.B., Hot-mix-plant, Boiler, transit mixer etc. to execute the



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

work at a time to perform all works simultaneously as per requirement of WBSEDCL.

57. Risk Purchase: In the event of failure of the contractor to execute the work timely and/or to the satisfaction of WEST BENGALSTATE ELECTRICITY DISTRIBUTION COMPANYLTD., the order/Letter of Award may be terminated prematurely and the balance work may be got done through any other agency at risk and cost of the contractor.

58. Additional Conditions of Contract:

- 1. The work shall be inspected time to time by WBSEDCL representatives. The contractor shall provide all facilities for such inspection free of cost. Notwithstanding any inspection of site, WBSEDCL shall have the right to reject any work not conforming to the specification without being liable for any explanation or compensation. The authorized representative of WBSEDCL shall have the free access to the work site, contractor site and store.
- **2.** During the execution of work, if any problem arises which is not covered by the specification, the contractor shall seek necessary clarification and instruction from WBSEDCL, such instruction shall be binding on the contractor and shall be observed in full.
- **3.** The contractor shall make his own arrangement for labour, construction equipment, tools and tackles and construction materials, construction water, office/ labour accommodation, water supply, sanitation etc.
- **4.** Electricity for construction purpose, is supplied by WBSEDCL, the charge shall be borne by the contractor at the rate specified by the WBSEDCL. The contractor can't claim any compensation for any failure in such supply caused due to any reason whatsoever in case of non-availability of electricity for construction purpose from WBSEDCL. The contractor will have to arrange for the same at his own cost.
- **5.** The contractor shall strictly follow the construction safety rules, regulations, and instructions issued from time to time in absence of any particular reference the contractor shall refer to relevant Indian standard and also the State Government rules and regulations.
- **6.** The contractor shall take all precautions during execution, especially while excavating underground works, such as cables, pipe lines, drains etc. and provide all possible protection to these works and in case any materials got damaged, rebuilt them at his own cost.
- **7.** All guarantee sand test certificates obtained by the contractor during the execution of work shall be transferred to the WBSEDCL before issue of final payment.
- 8. The contractor shall provide all necessary storage at the site in specified areas for all the materials such as timber, cement, lime and such other materials which are likely to deteriorate by the action of Sun, winds, rain or other natural cause due to exposure in the open in such manner that all such materials shall be duly protected from damage by weather or any other cause. All such stores shall be cleared after completion of the work and the entire site shall be clean and free from debris. All materials shall be stacked in such a manner as to facilitate rapid and easy checking of such materials.
- **9.** The cost of testing materials shall be borne by the contractor.
- **10.** All works are to be carried out with due regard to the convenience of the occupants of the premises or road users and with close coordination with other contractors who may be working in the area. All arrangements/ programs of work must be adjusted accordingly. All precautions must



Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhanagar,

Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

be taken to guard against chances of injury or accidents to other occupants, users and workers. The contractor must see that all damages to any property, which in the opinion of the controlling officer are due to work of the contractor, are promptly rectified as per direction and to his satisfaction. The construction work must be done in such away as not to dislocate or disturb any sewerage system and other existing structures.

- 11. It must be clearly under stood that WBSEDCL is indemnified by the contractor against payment of any compensation or award on account of any accident, injuries and damages and if any such payment has to be made by WBSEDCL under order of appropriate authorities, the same shall be recovered from the contractor.
- **12.** Any services if affected by the work must be restored by the contractor on emergency basis at his own cost.
- **13.** After completion of the work, the finishes shall be of high quality and of approved standard.
- **14.** No omission or ambiguities in the drawing or in the specification will relieve the contractor from responsibility for material and completeness of the work.
- **15.** The contractor shall not off-load the contract or part thereof to any subcontractor without obtaining written permission from the controlling officer of the work. In the event of sub-letting of contract or part thereof. In the event sub-letting of contract is permitted, the fact that such permission has been accorded shall not establish any contractual relationship between approved sub-contractor and WBSEDCL of any of his liabilities and obligations under the contract.
- **16.** A complete list of execution/ deviation from the bidder's scope of work shall be clearly indicated. Similarly, if any departure, commission of substitution from stipulated specification is made. This fact should be clearly indicated in the offer with reasons. However, WBSEDCL shall have the absolute discretion to summarily reject such offers.
- **17.** WBSEDCL's representative may during progress of work, order for re-execution of part or whole of the work executed, found not in accordance with the approved drawings / specifications/instructions. No extra claims shall be entertained for re-execution or altering or such work
- **18.** The contractor shall provide sufficient strong and stable staging as to ensure safety of the labourers and structures.
- **19.** The contractor shall dismantle and remove the staging and other temporary structures like stores, offices, labour camps etc. on completion of work, clear and clean the site where such temporary facilities were built and restore the same to original condition.
- **20.** Materials brought to the site shall not be removed from the site without the written consent of the WBSEDCL. The contractor shall submit well in advance for approval of samples, specimens as the WBSEDCL may demand from time to time. Any materials brought to the site and rejected by the WBSEDCL shall be removed by the contractor from the site of work immediately.
- **21.** All materials including reinforcing steel, cement for concrete work, sanitary, plumbing and carpentry fittings shall be procured after approval of brand and make by WBSEDCL.
- **22.** All bricks have to submerge in vats before put to use. Curing shall be done with proper care.
- **23.** The contractor has to make arrangement for temporary cover to enable civil construction works to continue if interrupted due to rains during monsoon.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101. VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091.

Website-<u>www.wbsedcl.in</u> CIN: U40109WB2007SGC113473

Regd. Office of WBSEDCL:

E-mail: <u>rm.malda@wbsedcl.in</u>

- **24.** If necessary extra items beyond S.O.W are executed the unit rate shall be as per the rates of PWD, West Bengal on the date of bid opening. Those items which are not covered under PWD rates shall be based on analysis of rate as applicable, on mutual agreement.
- **25.** Bar chart showing all activities needs to be submitted before commencement of work.
- **26.** Depth of the tube well, if any shall be complied with Public Health Engineering Directorate recommendations.
- **27.** All drawings supplied with the bid documents are tentative/ for guidance only.
- **28.** WBSEDCL shall not be liable under any circumstances for any accident/ untoward incidents, if happened during execution of works.
- **29.** The contractor shall submit test certificate from the appropriate authority for potable of drinking water indicating presence of arsenic and other chemicals, if any.
- **30.** If specification of any items of work is not covered in the bid documents the same shall be guided from PWD schedule of rates.
- **31.** All dismantled departmental materials shall have to be returned to store/disposed and stacked in a place (within 200m lead) provided by the purchaser without any extra cost to WBSEDCL.
- **32.** Mode of measurement shall be followed as described in PWDSOR, unless otherwise stated.



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101. Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Malda, WB- 732101. E-mail: rm.malda@wbsedcl.in

SPECIAL TERMS AND CONDITIONS:

1. Statutory Compliances:

- a) Issue of Work Permit: It has to be ensured that no contract labour shall be engaged without any Work Permit to be issued by an official not below the rank of Assistant Engineer to those contract labourers having requisite license / authorization to do such work. In the work permit name of the contract labour(s) engaged shall be provided. All such work permits shall contain certification regarding compliance of requisite safety precautions in regard to such work
- b) Each and every employee / worker engaged for the work shall be issued with Prescribed Photo Employment Card and their names shall be maintained in a separate Register. Copies of the same shall have to be submitted to this end for reference.
- c) Wages of the workmen shall have to be disbursed as per minimum wages Act vis-à-vis revised from time to time by Notification of the Labour Department, Govt. of West Bengal and reimbursement of difference of wages beyond the usual half yearly revised rate and / or at any point of time by Govt. of West Bengal shall be made subject to production of authenticated documents towards payment of the same to the labourers along with statutory compliances. Necessary wage Register for this purpose shall have to be maintained by the Contractor. Payment of wages to the workmen engaged by the Contractor should be made in presence of the authorized representative as may be specified by the Controlling Officer who shall in turn duly authenticate and sign the Payment Register.
- d) Payment of wages to each and every labour shall have to be ensured by 7th of each month against dated receipt thereof.
- e) The successful tenderer shall have to comply with the provisions of Employees Provident Fund Act and shall be liable for deduction of Provident Fund Contribution of their workmen & deposit the same with the P.F. Authorities along with equal share of Employer's contribution. Related documents authenticating deposition of PF in case of individual contract labour engaged shall have to be submitted once for the financial year (total or part, as the case maybe).
- f) The employees / workers engaged for the work shall have to be paid minimum payment of Bonus one time as per provision of the Payment of Bonus Act in each year and dated receipt of the same shall have to be submitted once in a year soon after disbursement of the same along with the monthly bill of the concerned period.

2. Acquaintance Roll:

The entrusted contractor shall have to submit copy of Acquaintance Roll in prescribed pro-forma to be supplied by WBSEDCL containing the names and details of the contract labourers, no. of days worked, amount of P.F. Subscription deducted/Employer's contribution and wages paid, dated receipt thereof of the same by each contract labourers along with the monthly bill. The payment will be made only on receipt of EPF Challan and goods and Service Tax Deposit Challan for the previous month along with wage sheet acknowledging the receipt of wages and indication of leave.

3. Risk & Coverage:

The Company (WBSEDCL) will be in no way held responsible/liable for any accident/mishap, if caused to any personnel of the agency during execution of work. The contractor shall ensure for workmen's compensation as per W.C. Act with an insurer approved by the owner and shall confirm such insurance during the contract period that any persons employed by him on the work are covered by insurance and shall produce to the concerned authority such policy or policies of insurance and receipt for payment of the current premium. If the contractor fail to effect and keep in force the insurance which he may be required to effect under the terms of the contract then and in any such case the owner may effect and keep in force any such insurance and pay such premium or premiums as may be necessary for the purpose and from time to time deduct the amount so paid by the owner as aforesaid from any money due or which may become due to the contractor or recover the same as a debt due from the contractor.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: <u>rm.malda@wbsedcl.in</u>

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

TECHNICAL SPECIFICATION: CIVIL WORKS

- 1. Indian Standards, Codes, Laws and Regulations: Throughout the duration of the contract, the materials, equipment, services, design and workmanship shall conform to applicable Indian codes, standards, laws and regulations in force in India, if not otherwise specified. It is the contractor's duty to acquaint him with all available Indian codes, standards, laws and regulations related to the works in any way and he shall procure and keep at the site a copy of each of such applicable documents.
- 2. System of Units: The IS system of units has been used throughout these specifications and this system of units shall be used consequently throughout the duration of contract for all technical or contractual purposes. The term "DAY" as used in these specifications means calendar day.
- 3. Quality of materials & General Standards of work: The Contractor under this contract commits himself to use first class materials and assumes full responsibility for the quality of all material incorporated or brought for incorporation in the work. The work shall be executed in accordance with best engineering practice and as per direction of WBSEDCL. In all possible cases, sample approved shall be done by the Contractor from WBSEDCL before bringing in the materials in bulk at site and the approved sample shall be well preserved at site at the risk and cost of the Contractor as a ready reference. Over and above, the submission of test certificate by the manufacturer, WBSEDCL may instruct further sample testing from Govt. Laboratories/ testing houses at the risk and cost of the Contractor for submission of test reports to become eligible for payment for those particular items used at work. In all possible cases, where the warranty of manufacturers is sought for by WBSEDCL. The Contractor shall submit the cross warranty in the form and manner as directed by WBSEDCL including workmanship etc. along with the manufacturer's warranty certificate. The relevant IS and PWD specification shall have to be complied with for all possible cases. In case of any anomaly / contradiction, decision of WBSEDCL shall be final and binding on Contractor. No extra claim shall be admissible for sample testing, sample approval, testing of sample at site etc. to the Contractor and shall be considered as deemed to have been included in the rates quoted by the Contractor.
- **4. Construction Power:** Construction power may be provided by WBSEDCL, if applied for by the Contractor as per prevailing rules and regulations of WBSEDCL. However, all charges for the construction power shall have to be borne by the Contractor. The relevant clause may also be referred to GCC in this regard. Alternatively, the Contractor shall have to arrange required capacity D.G. set at his own cost, risk and responsibility to work. Necessary permission to operate DG set to be obtained from the concerned authority by the Contractor. Arrangement of DG may also be kept for exigencies or power failure.
- **5. Scaffolding:** All scaffolding and ladders required for the proper execution of the work shall be provided by the Contractor. The scaffolding should be stout and strong to prevent any collapse or displacement. Proper measure for safety of workmen working on scaffolding should be taken by the Contractor.
- **6. Measurements:** The mode of measurements, wherever possible is specifically mentioned in these documents (Clause No.-18 of General Condition of Contract), where it has not been mentioned, it shall be as per provision of the PWDSOR and relevant Indian Standards IS 1200. All the measuring equipment, labour, manpower and other accessories necessary, shall be provided by the Contractor at his own risk and cost.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

- **7. Tools and Plant:** The bidder along with his bid furnish a list of tools, plant and machinery which he intends to use for the works (as per proforma, if enclosed with the bid document). The list should indicate the exact type of machine, its capacity, and year of manufacture, kind and capacity of propelling force, spare parts readily available and all other pertinent information. The Contractor is obliged to use all the machinery mentioned in his list mentioned or others as required and instructed if WBSEDCL considers it necessary.
- **8. Setting out:** The Contractor shall set out the building or other involved works after clearing the site and get the same approved by the owner. It shall be the responsibility of the Contractor to install substantial reference marks, bench marks etc. and maintain them as long as required by the owner. The Contractor shall assume the full responsibility for proper setting out, alignment, elevation and dimension of each and all parts of the work and he shall at his own expense make good any defects arising from errors in line and levels.
- **9.** Access to site: The Contractor shall at his own cost provide all approaches required for the purpose of carrying out the work in the most expeditious and efficient manner and shall remove the temporary arrangement on completion. He shall acquaint himself thoroughly regarding condition and suitability of public roads leading upto the limits of the premises and will provide vehicles for transportation of materials which meet the requirements of these road conditions. It shall also be responsibility of the Contractor to maintain at his own cost these roads till the construction is completed. The tenderer shall also acquaint himself with local laws and by laws and complying with all police and traffic requirements.
- **10. Dismantling:** The Contractor shall take out old damaged tar-felt from the roof, parapet etc. preparing the roof surfaces by removing all spoils, blisters, moss etc., all types of masonry work, all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish, stripping off worn out plaster from the working site and disposal of the same beyond the compound and cleaning the site in all respect as per direction of Engineer-in-Charge; in such a manner so that to avoid any accident at his own risk & responsibilities. They will take necessary step to prevent the damage the adjacent structure or existing services. They shall repair and make good any such damage at their own expense to the satisfaction of the owner. A suitable path for men and materials around the excavated pit should be maintained throughout the work. They shall also dismantle carefully terraced floor only (including floor finish if any) or lime terracing in third floor roof and removing rubbish as directed within a lead of 75m.
- **11. Disposal of dismantled materials:** All dismantled materials like rubbish, earth etc. from the working site shall be removed and disposed of the same beyond the compound with prior written permission of WBSEDCL in an approved manner and in conformity with the Municipal /Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer-in-Charge.
- **12. Plain & Reinforced Concrete:** Concrete and reinforced concrete work shall be carried out generally in conformity with the latest Indian Standards IS: 456 except for provisions indicated herein below. All work is to be carried out with utmost precision and up to date scientific know-how and the Contractor shall employ thoroughly competent staff to achieve the highest standards.
- **13. Cement:** Cement for the work shall be either of ordinary Portland Cement conforming to the latest Indian Standards IS:8112 1989 for 43 grade and IS:12269 -- 1987 for 53 grade or Portland Pozzolana Cement conforming to IS:1489 (Part 1) 1991-specification (fly ash based), IS:1489 (Part 2) 1991 -



(A Govt. of West Bengal Enterprise)

MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: <u>rm.malda@wbsedcl.in</u>

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

specification (Calcined clay based) or Portland Slag Cement as per IS:455 (with latest revision), as instructed & approved by the Engineer-in-Charge and/or Technical Controlling Officer for the work and of the best normal setting quality unless a quick setting quality is expressly instructed in the specifications or otherwise during the course of the work by WBSEDCL. Any field or laboratory test for cement, if asked for by WBSEDCL shall be carried out at the risk and cost of the Contractor as per provision of relevant IS codes. All bags and containers in which cement is packed shall be stored in a dry, weather-tight, properly ventilated structure with adequate provision against absorption of moisture. The Contractor shall at all times maintain for the inspection of WBSEDCL, a log book indicating the receipt of cement, brand and agent from whom obtained and the age of cement. Cement which has caked or perished by being wet or otherwise shall on no account be used on the work. Cement shall be consumed on the works in the same sequence as that of their receipt at site. Cement reclaimed from cleaning of bags or from spillage from containers or otherwise shall on no account be used. The cement is to be stacked in an orderly and accessible way to permit WBSEDCL physical verification of existing stock at all points of time. The Contractor has to ensure furnishing a copy of manufacturer batch test certificate along with every lot of supply. If so felt, WBSEDCL may instruct the Contractor for further testing of cement in Govt. laboratories/testing houses as has been detailed in the relevant clause of GCC, over and above the submission of test certificates at the risk and cost of the Contractor.

14. Fine aggregate: The term fine aggregate is used to designate aggregate in which the maximum size of particles is 4.75mm. The gradation of fine aggregate shall be as given below:

Square Mesh Sieve Opening(mm)	Percentage passing (By weight)
4.75	95-100
2.36	80-100
0.6	25-60
0.3	10-30
0.15	2-10
0.075	0-3

The percentage of deleterious substance in the fine aggregate shall conform to IS: 383, except that the fine aggregate shall contain no more than 0.1% by weight of deleterious (reactive) ferrous sulphide. The total percentage of deleterious substance must not exceed 5% by weight. Fine aggregate having specific gravity of less than 2.6 shall be rejected. Fine aggregates, when subjected to soundness test with a solution of sodium sulphate, after five cycles of tests, shall not suffer a loss of weight in excess of 10 per cent. Fineness modulus shall be 2.6 ± 0.4 . Fine aggregate, upon delivery to the batching plant, shall have uniform and stable moisture content. The amount of moisture shall be less than 6% by weight, and shall not vary by more than 0.5% per hour.

- **15.** Coarse Aggregate: The term coarse aggregate is used to designate aggregate which is retained on sieve opening 4.75mm. The coarse aggregate shall be well graded and its gradation will be decided based on the laboratory tests to obtain dense mass of concrete. The gradation will be approved by the Engineer-in-Charge before production of the concrete. Coarse aggregates shall be stored separately in stockpiles or bins in such a manner to avoid intermixing of different size of aggregates. The storing shall be done in following sizes: 4.75-10 mm, 10-20 mm and 20-40 mm. The percentage of deleterious substance in the coarse aggregate shall conform to IS: 383, except that the coarse aggregate shall contain no more than 0.3% by weight of deleterious (reactive) ferrous sulphide. When subjected to following tests as specified in IS: 2386 (Part IV), the coarse aggregate shall comply with following requirements:
- (a) Aggregate Crushing Value Less than 45%
- (b) Aggregate Impact Value Less than 45%
- (c) Los Angles abrasion value Less than 50%

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

When subjected to sodium sulphate soundness test, coarse aggregate shall not suffer a loss of weight in excess of 12% after five cycles. Coarse aggregate shall be hard, dense, durable, uncoated rock fragments. Rock having absorption greater than 3% or specific gravity less than 2.5 shall not be used. Aggregate delivered to the batching plant shall have uniform and stable moisture content. The nominal maximum aggregate size in relation to the structure dimension shall not be larger than:

- a) 0.20 of the narrowest dimensions between the sides of forms,
- b) 0.75 of the minimum clear spacing between the reinforcing bars,
- c) 0.25 of the slab depths.
- **16. Aggregate Storage:** Aggregates shall be stored in a manner so that each size of aggregate is stored separately in free-draining piles in a manner that reduces breakage, deterioration, contamination and segregation to a minimum. Storage arrangements shall be subject to acceptance by the Engineer-in-Charge. The Contractor shall maintain sufficient aggregate storage at the Site at all times to permit continuous placement of concrete in accordance with the contractual time schedule. The moisture content of aggregates shall be controlled as far as practicable, by wetting the stockpiles and by adequate drainage. All aggregate shall remain in a free-draining stockpile for at least 12 hours prior to use. The preparation of stockpile areas, the storage of processed aggregates and the disposal of any rejected material shall at all times be subject to the approval by the Engineer-in-Charge. Materials shall be removed from stockpiles by methods which minimize segregation and crushing. No fine aggregate from the bottom 500 mm of the stockpile shall be used for mixing concrete.
- **17. Water:** A reliable and adequate water supply shall be installed and maintained by the Contractor for washing of aggregates, manufacturing and curing of concrete. The water shall be clean and free from harmful quantities of oil, acids, alkalis, sugar, salt, silt and other organic matters and shall conform to IS: 456. Water shall contain no more than 1,000 mg/l of sulphates (SO4), not more than 100 mg/l of chlorides (Cl), and shall have a turbidity limit of not more than 1,000 ppm. Adequate water storage shall be provided at the batching plant to ensure smooth concrete production. Contractor shall familiarize himself with source and quality of water available. Attention is drawn to the possible requirement of settling pond and other facilities that he may be required to provide.
- 18. Types of Concrete, Strengths etc.: Denomination of concrete classes is based on the characteristic compressive strength (in Newton per square mm) and maximum aggregate size. The characteristic compressive strength is defined as the compressive strength of 150 mm cube as measured at 28 (twenty-eight) days. The strength shall comply with the requirements of IS: 456. The following table shows, in general, the anticipated classes of concrete required in various sections of work. The specific class of concrete to be used in each area will be shown on the Construction Drawings or designated by Engineer-in-Charge. Much before commencement of any concreting of permanent works, the Contractor shall start the testing of materials, propose the composition of concrete mixes and prepare trial mix of each of the proposed concrete class. The Contractor shall prepare the trial mixes using the cement, water, aggregates and admixtures intended for the work and which conform to the requirements specified in this Section. The contractor shall determine, in accordance with IS standards and/or ACI Manual of Concrete Practice, the mix proportions for the designated classes of concrete. The contractor shall submit the test reports to the Engineer-in-Charge for approval. This preliminary test program shall include the determination of following parameters:
- a) Cement properties,
- b) Characteristics of aggregates,
- c) Mix water properties,
- d) Admixture properties,
- e) Proportion of aggregate ranges in the mix,

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

- f) Proportion of uncrushed to crushed aggregates,
- g) Cement content,
- h) Water-cement ratio(W/C),
- i) Workability of concrete mixes,
- j) Compressive and tensile strength,
- k) Entrained air,
- l) Density,
- m) Water-tightness.
- **19.** Curing & Protection of Concrete: Plant for curing and protection of concrete shall be available at the location of each concrete placement before concrete placement is started. The water used for curing shall meet the requirements for water used for mixing concrete. The curing water temperature shall not exceed 25oC. Exposed surface of concrete which have been finished as specified shall be protected from the direct rays of the sun for at least 2 days after placing. Freshly placed concrete shall be protected from rainfall. Exposed surfaces shall be kept moist or the moisture in the concrete shall be prevented from evaporating for at least 14 days after placing by means of continuous sprinkling or spraying with water, or by other methods approved by the Engineer-in-Charge. Care shall be taken not to disturb the steel reinforcement projecting from any placement for at least 24 hours after the completion of such placement. The Contractor shall not move any load on concrete surfaces which in the opinion of the Engineer-in-Charge have not attained sufficient strength. In case loads are required to be moved, the Engineer-in-Charge may permit Contractor to do so on condition that Contractor provides the means for protecting the concrete surface subject to approval of the Engineer-in- Charge. The Engineer-in-Charge may permit the use of curing by means of membrane forming compounds. Sealing compounds proposed by the Contractor will be subject to sampling and testing and will have to be approved by the Engineerin- Charge. Curing compounds shall be applied according to the manufacturer's recommendations to provide a continuous uniform membrane over all area. Curing compounds shall be applied only after moist curing has been carried out for at least 24hours.
- **20. Tests for determination of strength of Reinforced concrete:** As will be apparent from the Bill of Quantities, the strength of concrete specified is the criterion and the Contractor shall make every effort to obtain the specified strengths by good quality control. In case of concrete which does not obtain the specified strength at 28 days, such work shall be demolished and reconstructed to obtain the requisite strengths all as directed by WBSEDCL. To determine whether concrete in any particular part of the work is of the requisite strength or not, test cubes (works test cubes) shall be made from samples collected from the concrete being poured for the particular part and determined as per acceptance criteria detailed hereinafter. The salient features for the collection of samples are as follows
 - **a. Quantum of cubes and testing:** The decision of WBSEDCL in this regard shall be final and binding. Cube testing shall be done at site regularly and at least 20% of this testing shall be carried out in the reputed laboratory (as approved by the Owner) as defined in the relevant clause of GCC. Testing machine with valid calibration certificate to be kept at site for crushing of cubes. The testing shall be duly witnessed and approved by WBSEDCL.
 - **b.** All costs to carry out tests at field as well laboratory shall be borne by the Contractor.
 - **c.** The size of cubes to be prepared and tested shall be 15 x 15 x 15 cm. (6" x 6" x6").
 - **d.** The minimum number of cubes to be collected from each sample as detailed below shall be six. Three cubes each are intended for testing at 7 and 28 days respectively and determining the strength.
 - **e.** Cubes tested at 7 days should give strength of not less than 70% of the corresponding strength at 28 days. It shall however be expressly understood that the test results at 28 days only shall govern

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

and the 7 days tests are intended to obtain a fair idea only.

- **f.** Relevant IS codes including IS: 456 (latest revision) shall be followed by the Contractor. All costs for sampling and field as well as laboratory testing shall be borne by the Contractor.
- **21.** Tor Steel Reinforcement:-TMT bar for reinforcement shall be of tested quality and shall conform to the relevant Indian Standards (IS: 1786). Reinforcement shall be fabricated to shapes and dimensions shown on the drawing and shall be placed where indicated on the drawings or required to carry out the intent of drawing and specifications or as directed by WBSEDCL. Before placing, reinforcement shall be thoroughly cleaned of loose rust, coating etc. This would result in reducing or destroying the bend. Oiling the bars to clean them is strictly prohibited. Bending, straightening, cutting etc. operations shall be carried out in a manner not injurious to the material. List of manufacturers for reinforcement shall be as per BOQ and/or as per PWDSOR (Latest amendment) and/or list given in the technical specification of the "Bid Document" and finally, as instructed in writing by WBSEDCL. All reinforcement shall be bent cold. Unless otherwise directed, reinforcement shall not be spliced at points of maximum stresses. WBSEDCL shall be informed well in advance before such splicing is taken up. Laps and splicing shall conform to the latest Indian Standards. Reinforcement shall be accurately tied at all intersections and laps with 16 SWG soft drawn binding wire, such that the reinforcement will give a rigid structure. Binding wire will not be measured or accounted for separately. The Contractor's rate for reinforcement will be measured and paid for according to bending lists without allowances for cutting, wastages, binding wire etc. Authorized laps, hooks, chairs, spacers etc. shall, however be accounted for. In case, the Contractor or WBSEDCL desires to resort to welding, there shall however be made as if the laps have been provided and no extra claim whatsoever shall be admissible on this account. The relevant IS code and schedule of specification shall be followed and applicable for the case also. Reinforcement shall be assembled in place with proper concrete cover blocks to suit various covers as required. The Contractor has to ensure furnishing of manufacturer certificate with every lot of supply. If felt necessary, WBSEDCL may ask for testing of reinforcement sample, over and above, submission of manufacturer's certificate, in Govt. laboratories/ testing houses as detailed in the relevant clause of GCC, at the risk and cost of the Contractor.
- 22. Brick Masonry & Plastering: Brick shall be soaked in clear water for at least six hours in a vat before use. Bricks shall be laid in English bond unless specified otherwise. No half or quarter brick shall be used except as closers. Brick shall be accurately raised to plumb. Brick work shall be raised uniformly all round and no part shall be raised more than 1 metre above another at any time, and the work shall be properly toothed and racked back. In case of 125 mm thick brick walls, wire mesh shall be provided in every third course as per relevant specification and as instructed by WBSEDCL. The wire mesh shall be properly bedded in mortar, as directed. Joints in brick work shall not be more than 10 mm. thick. Brick work shall not be raised more than 10 courses a day. The work shall be kept watered thrice a day for 10 days and afterwards twice a day for 3 weeks. All joints shall be thoroughly flushed with mortar at every course. Care shall be taken to see that bricks are properly bedded and all vertical joints completely filled to the full depth. The jointed of brick work shall be raised out to a depth not less than 10mm. as the work proceeds. The surface of brick work shall be cleaned down and watered properly before the mortar sets. Plastering work in general shall proceed from top to bottom. An entire unobstructed area shall be plastered in one operation. The surface to be plastered shall be thoroughly cleaned, watered and roughened to provide key. Joints in brick work shall be raked out and cleaned. The surface shall be watered and well wetted for at least 24 hours before the commencement of work. The entire plastered work shall be truly vertical and to proper lines and levels. All exposed angles shall be carefully flushed to provide neat and even surface. Any work that does not conform to approved samples or is not to the

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

WBSFDLL

E-mail: <u>rm.malda@wbsedcl.in</u>

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

satisfaction of WBSEDCL shall be rejected and the Contractor shall be liable to redo the work at his own cost. Cement sand plaster will be used. Sand will be coarse or fine (Zone-III). Where waterproofing compound is specified to be provided in mortar for plaster, approved integral waterproofing compounds shall be used. These shall be used and plastering work shall be carried out strictly as per manufacturer's recommendations.

- **23. Timber:** The timber used for structural purposes shall conform to IS:883.
- **24. Form work:** All materials shall comply with the requirements of IRC: 87. Materials and components used for formwork shall be examined for damage or excessive, deterioration before use/re-use and shall be used only if found suitable after necessary repairs. In case of timber formwork, the inspection shall not only cover physical damages but also signs of attacks by decay, rot or insect attack or the development of splits. Forms shall be constructed with metal or timber. The metal used for forms shall be of such thickness that the forms remain true to shape. All bolts should be countersunk. The use of approved internal steel ties or steel or plastic spacers shall be permitted. Structural steel tubes used as support for forms shall have a minimum wall thickness of 4 mm. Other materials conforming to the requirements of IRC: 87 may also be used if approved by the Engineer.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

2.

3.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

ANNEXURE-A

<u>Pro-forma for Contract Agreement</u> (To be executed on Non-Judicial Stamp Paper of Rs. 100/-)

Limited(WBSEDCL), a statutory Body constituted by the Govt. of West Ber	in the year between West Bengal State Electricity Distribution Company ngal having its head office at "Vidyut Bhaban", Block-DJ, Sector-II, Salt Lake City, I unless excluded by or repugnant to the context be deemed to include its successors AND
	ss excluded by or repugnant to the context be deemed to include his heirs, executors,
administrators, representatives and assigns) of the OTHER PART.	
WHEREAS the Company invited tenders vide Tender Notice No	hereto)for"
AND WHEREAS in pursuance of such invitation for tenders, the contractor	or submitted a tender vide no,
	s opened on(The tender offer is in custody of the Company
at present). AND WHEREAS AFTER consideration of the tender submitted by the contractor and placed Letter of Award no	ractor with clarification(s), the Company accepted the said tender submitted by the
NOW, THEREFORE, the Company and the contractor agree as follows:	··
The Contractor agrees to undertake the work of—"	
of Award no	datereferred to above.
The Company agrees to pay the Contractor as per Letter of Award no	
date	
Both the Contractor and the Company agree that for the purpose of jurisdiction	on in the court in regard to any dispute arising out of this agreement, this agreement
shall be deemed to have been executed within the jurisdiction of the original si	•
IN WITNESS WHEREOF the parties have hereunder affixed their signature o	n the day, the month and year written as above.
SIGNED, SEALED AND DELIVERED	
Contractor	Company
1)	1)
Witness	Witness
2)	2)
Witness	Witness

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

ANNEXURE-B

SPECIMEN COPY OF INDEMNITY BOND

(To be executed on Non-Judicial Stamp Paper of Rs. 100/-)

Company Limited., a government Company within the meaning of sec.617 of the Indian Company's act having registered office at Bidyut Bhavan, Block-DJ, Sector-II, Salt Lake City, Kolkata-700091 (hereinafter called as OBLIGEE, which expression shall mean and include it's legal representative, administrators assigns.

WHEREAS OBLIGOR/OBLIGORS has /have been awarded to execute the job/works under letter

AND WHEREAS according to the condition of the contract the OBLIGOR/OBLIGORS is under obligation to execute this Indemnity Bond before the commencement of actual execution and OBLIGOR/OBLIGORS is/are aware that unless this Indemnity Bond is executed in accordance with the condition of contract before the actual execution in accordance with law the OBLIGEE shall have the power to deem that actual work has been started within the meaning of the contract before the execution of this Indemnity Bond.

NOW THIS INDENTURE WITNESS THAT I / We the OBLIGOR/OBLIGORS do hereby undertake

- 1. THAT the OBLIGEE shall not be held responsible for any type of accident which may take place during the course of work undertaken by the OBLIGOR/OBLIGORS.
- 2. THAT the OBLIGOR/OBLIGORS will take adopt all safety norms in respect of each and every workmen labour personnel according to the rules or to the satisfaction of the OBLIGEE in all cases.
- 3. THAT the OBLIGOR/OBLIGORS undertakes to engage only those labour worker or any other personnel whether skilled or unskilled or any other person whether in technical management or non-managerial or any other capacity in the area covered under Employees' State Insurance Act, 1948 who has/have insurance coverage within the meaning of Employees State Insurance Act, who does / do not has/have insurance coverage within the meaning of Employees State Insurance Act.
- 4. THAT the OBLIGOR/OBLIGORS further undertakes to engage only those labour worker, or any other personnel, whether skilled or unskilled, whether in technical, managerial or non-managerial or any other capacity in the area NOT covered under Employees' State Insurance Act who has life insurance for the sum assured equivalent to the amount of Compensation under the Employees' Compensation Act in case of accidental death or inquiry and such insurance has been effected by the OBLIGOR/OBLIGORS.
- 5. THAT the OBLIGOR/OBLIGORS undertakes / undertake to indemnify and keep harmless the OBLIGEE from all claims action proceedings and of risk damage danger to any person whether belonging to/or not belonging to OBLIGOR/OBLIGORS.
- 6. THAT the OBLIGOR/OBLIGORS shall keep harmless the OBLIGEE from all claims compensation damages any proceedings in respect of any of its employee/workmen under the Workmen Compensation Act. Or any other laws for the time being in force.
- 7. THAT if during the course of execution of work as stated in the letter mentioned hereinabove issued by the OBLIGEE, it is found that the OBLIGOR/OBLIGORS has/have not complied with guidelines/formalities within the meaning of Employees' State Insurance Act or Workmen Compensation Act or any other laws relating to the Labour Welfare for the time being in



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

force, and also has not observed the safety norms in accordance with the law to the satisfaction of the OBLIGEE, the OBLIGEE shall have the right to stop the execution of work/job and the period of such stoppage shall continue till adequate safety and other compliance mentioned herein above under the labour welfare legislation have been observed and such period of stoppage shall not be taken into account for the calculation of the total period of completion of work for which the OBLIGOR/OBLIGORS is responsible to complete the work/job and it will be deemed that discontinuance was due to default of OBLIGOR/OBLIGATOR.

- 8. THAT, if at any time due to exigency, the OBLIGEE i.e. the West Bengal State Electricity Distribution Company Limited as the Principal Employer, becomes liable to pay any such compensation mentioned herein above, whether on failure of the OBLIGOR/OBLIGORS or for any other reason, the OBLIGEE shall have the right to recover the said amount from any amount receivable by OBLIGOR/OBLIGORS or any bank guarantee deposited or anything payable whether in connection with this contract or other contract by the OBLIGEE to the OBLIGOR/OBLIGORS
- 9. THAT the OBLIGOR/OBLIGORS is/are aware and accept that for the persistent or repeated violation of any condition mentioned in this Indemnity Bond, the OBLIGEE shall have right to terminate the contract of work issued by the OBLIGEE to OBLIGOR/OBLIGORS.

SIGNED AN	ND DELIVERED	
BY THE OF	BLIGOR/OBLIGOR	
Signature of	WITNESS	
1.	Name,	
	Designation	
	Signature	
2.	Name,	
	Designation	
	Signature	

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL:
VidyutBhavan,
Block-DJ, Sector – II,
Bidhannagar,
Kolkata – 700 091.
Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

ANNEXURE-C

PROFORMA OF BANK GUARANTEE FOR CONTRACT PERFORMANCE

(The non-Judicial stamp paper of Rs.100.00 should be in the name of issuing bank)

Net:	Dank Guarantee No
	Date
To	
The Regional Manager,	
Regional Office, Malda	
West Bengal State Electricity Distribution	Co. Ltd.
Malda	
Dear Sirs,	
which expression shall unless repugnant assigns) having awarded to M/S	to the context or meaning thereof include its successors, administrators and
Head Office at(hereina context or meaning thereof, include its undertake to pay the Owner, on demand an	(Name & Address) having its after referred to as the "Bank", which expression shall, unless repugnant to the successors, administrators, executors and assigns) do hereby guarantee and my or all monies payable by the Contractor to the extent of Rs
Any such demand made by the Owner of	on the bank shall be conclusive and binding not withstanding any difference

Any such demand made by the Owner on the bank shall be conclusive and binding not withstanding any difference between the Owner and the Contractor or any dispute pending before any Court, Tribunal, arbitrator or any other authority. The Bank undertakes not to revoke this guarantee during its currency without previous consent of the Owner and further agrees that the guarantee herein contained shall continue to be enforceable till the Owner discharges this guarantee.

The Owner shall have the fullest liberty without affecting in any way the liability of the Bank under the guarantee from time to time to extend the time for performance or the Contractor. The Owner shall have the fullest liberty, without affecting this guarantee, to postpone from time to time the exercise of any powers vested in them or any right which they might have against the contractor and to exercise the same at any time in any manner and either to enforce or to for bear to enforce any covenants, contained or implied in the Contract between the Owner and the Contractor or any other course or remedy or security available to the Owner. The Bank shall not be relieved of its obligations under these presents by any exercise by the Owner of its liberty with reference to the matters aforesaid or any of them or by reason of any other act of omission or commission on the

(A Govt. of West Bengal Enterprise) MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Part of the Owner or any other indulgences shown by the Owner or by any other matter or things whatsoever which under law would, but for this provision have the effect of relieving the Bank.

The bank also agrees that the Owner at its option shall be entitled to enforce this guarantee against the Bank as principal debtor, in the first instance without proceedings against the Contractor and not withstanding any security or other guarantee the Owner may have in relation to the Contractor's liabilities.

shall remain in force upto and includingtime for such period may be desired M/S	liability under this guarantee is restricted to Rsand it**(day/month/year) and shall be extended from time toon whose behalf this guarantee has been given unless a*(day/month/year) we shall be discharged from all
Dated this day	
of20	at
WITNESS	
(Signature)	(Signature)
(orginature)	(Signature)
(Name)	(Name)
(Name)	(Name)
(Official Address)	(Official Address)
(Official Address)	(Official Address)
Attorney as Power of Attorney No	
Data	

- Till 3 (Three) months after the validity of the Bank Guarantee.
- Upto 3(Three) months after the expiry of warranty/guarantee period.

Notes :-

- 1. The Stamp Paper of appropriate value shall be purchased in the name of issuing Bank.
- 2. The sum shall be 10% (Ten Percent) of the Contract Price.

The Performance Bank Guarantee /Security Deposit Bank Guarantee shall be valid as per terms of contract. A period of 3(Three) months should be added as claimed period from the last date of validity of the Bank Guarantee.



(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

ANNEXURE-C

WHEREAS				
WHEREAS				
Contract No				
Contract No				
Contract No	WHEREAS			(Name and
AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee a Scheduled Commercial Bank for the sum specified therein for 'ADDITIONAL PERFORMANCE SECURITY DEPOSIT' compliance with his obligation in accordance with the Contract. NOW THERE FORE we	Address of the Contractor)(hereaf	ter called "the Contractor")	nas under taken, in pursuance of	
AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee a Scheduled Commercial Bank for the sum specified therein for 'ADDITIONAL PERFORMANCE SECURITY DEPOSIT' compliance with his obligation in accordance with the Contract. NOW THERE FORE we	Contract No.	Dated	to execute	and brief
a Scheduled Commercial Bank for the sum specified therein for 'ADDITIONAL PERFORMANCE SECURITY DEPOSIT' compliance with his obligation in accordance with the Contract. NOW THERE FORE we	(name of Contract)	called "the Contract").		
NOW THERE FORE we	a Scheduled Commercial Bank for	or the sum specified therein	n for 'ADDITIONAL PERFORMA	
(in words). We undertake to pay you, upon your first written demand a without cavil of argument, a sum within the limits of	branch) have agreed to give the Co	ontractor such a Bank Guara	antee.	neate the name of the ban
(indicate the name of the bank and branch) hereby waive necessity of your demanding the said debt from the contractor before presenting us with the demand. We	NOW THERE FORE we	nd responsible to you on be	(indicate the name half of the Contractor, upto a total oords). We undertake to pay you, up	of the bank & branch) he f Rs(amount on your first written demand
(indicate the name of the bank and branch) further agree to pay to you any money so demanded not withstanding any dispute or disputes raised by the contractor(s) in any suit or proceeding pend perfore any court or Tribunal the present absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We (indicate the name of the bank and branch) further against no change or addition to or other modification of the terms of the Contract or of the works to be performed there under on any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability for payment.	without cavil of argument, a sum vito show grounds or reasons for yo	within the limits of ur demand for the sum spec	(amount of guarantee) as aforesaid ified therein.	without your needing to prov
(indicate the name of the bank and branch) further agree to pay to you any money so demanded not withstanding any dispute or disputes raised by the contractor(s) in any suit or proceeding pend perfore any court or Tribunal the present absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We (indicate the name of the bank and branch) further against no change or addition to or other modification of the terms of the Contract or of the works to be performed there under on any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability for payment.	We		_(indicate the name of the bank	and branch) hereby waive
the present absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We	necessity of your demanding the s	aid debt from the contractor	before presenting us with the dema	nd.
the present absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We	We		(indicate the name of the bank and b	oranch) further agree to pay to
the present absolute and unequivocal. The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We	you any money so demanded not	withstanding any dispute or	disputes raised by the contractor(s)	in any suit or proceeding pen
The payment so made by us under this bond shall be a valid discharge of our liability for payment there under and contractor(s) shall have no claim against us for making such payment. We	before any court or Tribunal		the present absolute and unequivoc	al.
any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liabi	The payment so made by us ur	nder this bond shall be a		or payment there under and
any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liabi	Wo		(indicate the name of the	hank and branch) further a
any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liabi	we that no change or addition to or o	ther modification of the ter	ms of the Contract or of the works t	o be performed there under a
,				

(A Govt. of West Bengal Enterprise) MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 732101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector - II, Bidhannagar, Kolkata - 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

This Guarantee shall be valid upto		it come into force with immediate
		on of the work under the stated contract plus claim ioned above our liability against this guarantee is
restricted to Rs.	(Rupees) and unless a claim in writing
is lodged with us within the validity period	i.e. upto	of this guarantee all our
liabilities under this guarantee shall cease t	o exist.	
Signed and sealed this day_of_	2021	at
	SIGNED, SEALED AND DELIVER	ED
	For and on behalf of the BANK	
		(Signature) (Name)
by:		
		(Designation) (Code Number) (Address)
NOTES:		

- 1. The bank guarantee should contain the name designation and code number of the officer(s) signing the guarantee.
- 2. The address, telephone number and other details of the Head Office of the Bank as well as of issuing Branch should be mentioned on the covering letter of issuing Branch.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

SPECIAL CONDITIONS OF CONTRACT AND SPECIFICATION FOR ELECTRICAL WORK

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-<u>www.wbsedcl.in</u>

CIN: U40109WB2007SGC113473

SPECIAL CONDITIONS OF CONTRACT AND SPECIFICATION FOR ELECTRICAL WORKS

- 1. General: These Special Conditions of Contract supplement the preamble and General Instructions, General Condition of Contract, Bill of Quantities and basic rates and Technical Specifications and tender drawings (if any) enclosed thereto, and shall be considered as part of the Tender Papers. Where the provisions of these Special Conditions of Contract are at variance with General Conditions of Contract, the Provisions of these Special Conditions of Contract shall prevail. The several documents forming the tender are to be taken as mutually complementary to one another. Detail drawings (if any) shall be followed in preference to small-scale drawings and figured dimensions in preference to scaled dimensions. If there are varying or conflicting provisions and the documents forming part of the contract, the Engineer-in-Charge shall be the deciding authority with regard to the intentions of the provisions and his decision shall be final and binding on the contractor. The Employer reserve the right to exclude any of the Schedule Items on reasons of the rates not being reasonable or subsequent change of design for evaluation of tender and deciding the contract. The Contractor may be required to carry out any additional or alteration work other than the specified in the Schedule of work/bill of quantities as and when required, by the 'Employer' within the completion period of the project.
- **2. Scope of Work:** The works to be governed by this contract shall cover designing and transportation up to destination, safe custody at site, insurance, erection, testing and commissioning of the following
 - i. Main Switchgear panel connecting cables of both incoming and outgoing feeder's etc.
 - ii. Laying of L.T. underground cables from Switch Room to various buildings, feeder pillar-boxes, street light poles, etc.
- iii. Electrification of new/old buildings, yard lighting, quarters, outer spaces including renovation works. Earthing of installations as per relevant Indian Standard Specifications. All other earthwork and masonry work required to be done concerning the electrical works.
- **3. Drawings**: Contractors shall prepare all the detailed design and working drawings and submit them to the Employer for approval within, 15 days from the date of award of contract. The working drawings shall be furnished in triplicate furnishing physical dimensions of the equipment, constructional details, disposition of bus bar, terminal connection etc. The electrical layout, clearly indicating the electrical clearances, cable run layout with Schematic diagram shall be furnished in triplicate for approval.
- **4. Execution of Work:** All the works included in electrical schedule of works i.e. power panels, distribution boards, equipment layout, conduits layout, electrical wiring, street lighting, cable laying, earthing etc., have to be done as per approved drawings and directions given at site by the Engineer-in-Charge.
- **5. Electrical License:** Only a Contractor holding a valid Electrical License issued by the "State/National Government for carrying out the installation work of the voltage classes involved, under the direct supervision of the persons holding valid certificates issued or recognized by the State/National Government shall carry out the work.
- **6. Inspection:** The inspection officer(s) for this contract shall be nominated by the Employer and notified to the

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

contractor. The cost of the inspection will be on Employer's account subject to any other provisions contained hereunder elsewhere in the contract. One week's notice must be given by the Contractor to the Inspecting Engineer to take Inspection. The Contractor shall provide without any extra cost of the Employer all materials, equipment, tools, labour maintenance of every kind which the Employer's Inspecting Engineer may consider necessary for any test examination to be made at the Contractor's premises and at site and shall pay all attended thereon. All the equipment and materials shall be tested / inspected by the Employer or its authorized Inspecting Engineer approved before they are installed / used in the execution of the works covered in the contract. If the Contractor any equipment / materials without the prior approval of Employer, those are liable to be rejected. The exact position of all switch boards, OPDs and all runs-of-mains, sub-mains and distribution wiring to individual points including exact positions of all light fittings and switch-boards shall be first worked on the buildings and shall have t1 approved by the Engineer-in Charge before actual commencement of work.

The Inspecting Engineer or his authorized Representative shall have at all times access to the Contractor's premises and shall have the power to:

- i. Inspect and examine the materials and workmanship of the work at any time during the manufacture at the manufacturer's premises or in the premises of the contractor or at the site of the erection.
- ii. Reject any part of the work submitted by the Contractor as not being in accordance with the contractor.
- iii. Reject the whole of the work including equipment tendered of inspection if after the inspection of such portion as he may, in his discretion think fit. He is satisfied that the same is unsatisfactory.
- iv. Mark the rejected equipment with a rejection mark so that the same may be easily identified.
- v. Re-inspect at the time of erection at site any equipment both previously inspected and approved by the inspecting Engineer at the Contractor premises. Notwithstanding any approval given earlier, the Contractor shall make good such rejections made based on such re-inspection at site to the satisfaction of the Engineer.
- vi. The decision of the Inspecting Engineer as regards to the acceptance or rejection of equipment /work shall be final and binding to the Contractor.
- **7. Consequence of Rejection:** On the equipment /assemblies being rejected by the Inspecting Officer of the Employer at destination the Contractor shall replace such rejected equipment/assemblies of the work forthwith but in any event not later than a period of 2 (two) weeks in the case of minor equipment and 4 (four) weeks in the case of major equipment from the date of rejection. The Contractor shall bear all the costs of replacement including freight, etc., but without being entitled to any extra time on this account. The decision as to whether the equipment is to be classified as Minor or Major for the purpose of this clause shall be that of the Engineer and it is not questionable.
- **8. Installation:** All works connected with and inclusive of installation and erection under this contract shall be done in accordance with the standard and established methods of installation and erection of electrical equipment and shall comply with relevant Indian Electricity Rules, National Electrical Code, BIS Codes of

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Specifications and Standards. The work shall also be strictly in accordance with the instructions / recommendations of the manufacturers. The equipment shall be leveled carefully before being fixed finally in position- All fragile and sensitive equipment shall be protected adequately and handled carefully during installation and erection.

9. Commissioning Tests: As soon as the installations are ready for commissioning / sub-station, the Contractorshallarrangeforallthetests/inspectionasrequiredbytherelevantISS and / or IE Rules and advice the Employer and others concerned. Employer shall depute their Inspecting Officer for witnessing the tests and to carry out inspection independently and also jointly with other concerned agencies where ever necessary and only after the installation passes the required tests and inspection, it should be commissioned /energized.

The Contractor shall take full responsibility for these tests. For site tests the Employer where possible, may permit the Contractor for the purpose of testing, the use of any instruments / apparatus and electric power which the Employer can conveniently work not complying with the specifications, the Employer at their discretion ask the Contractor to pay the cost of providing the additional energy required. The Contractor shall provide all apparatus and energy, which may be required for drying out the equipment in a manner approved by the Employer. If, by reasons of the Contractor failing to comply with any of the provisions of this clause, any of the said tests are to be repeated the Contractor shall pay all fees and expenses in connection therewith.

Visual Inspection shall include checks for satisfactory workmanship, all connections, painting, plastering, cleanliness of all fittings etc., and compliance with Indian Electricity Rules.

The ammeters, voltmeters, and energy-meters shall be checked for their calibration, scale, accuracy, etc. for compliance with the specified requirement.

Manufacturer's Test Certificates shall be furnished as evidence that type tests have been made in accordance with IS: 3231. Type test results together with appropriate drawings and records of any relevant alteration, which may have been made to any relay after the type test, shall be made available.

- i. Certificates of compliance to routine test shall also be furnished.
- ii. Routine tests shall be carried out at manufacturer premises before commissioning in compliance with 15:3231
- iii. Routine-tests are to be carried out on presence of Engineer-in-Charge and test certificates are to be submitted.

All cables shall be tested at manufacturer's works in compliance with relevant standards. All cables and connections after erection shall be tested as required by the Employer for:

- i. Pressure Test.
- ii. Insulation Test.

Earth resistance shall be measured separately for each earth electrode and when they are connected together and to the equipment recorded.

10. Warranty: Contractor shall guarantee that all the equipment and the works executed under this contract shall be free from all defects and faults in materials, design, workmanship and manufacture and shall be of acceptable standards for the contracted work and in full conformity to the technical specifications, drawings and other contract stipulations.

The Contractor's liability in respect of any complaint defect and/or claim shall be limited to the execution, installation and erection of replacement parts free of charge, or the repair of defective parts only to the extent that such replacement or repairs are attributable to or arise from faulty workmanship or design or material in the manufacture of the equipment/stores, and or negligence in any manner and also in the event of failure of the

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

equipment to perform as intended.

The Contractor shall, if required, replace, repair, execute and / or install the goods or such portion thereof as in rejected by the Employer free of cost at site or at the option of the Employer the contractor shall pay to the Employer the value thereof and such other expenditure and damage as may arise by reason of the breach of the conditions therein specified.

If, any defect is not rectified satisfactorily within the above mentioned one month, the Employer may proceed to do the work at Contractor's risk and cost and without prejudice to any other rights of the Contractor under this contract.

If the Contractor so desires, the replaced parts can be taken over by him or his Representative for disposal as he deems fit within a period of one month from the date of replacement of goods/parts at the expire of this period, no claim whatsoever shall lie on the Employer.

The Employer may, at their discretion recover the ground rent for the goods/parts which have been rejected during the warranty period for the specified period of one month, if the rejected materials are not taken over within that period one month, by the Contractor or his Representative.

The warranty herein contained shall not apply to any material which have been repaired or altered by the Employer, or on their behalf in any without the consent of the Contractor so as to affect its strength, performance and reliability or to any defects to any part due to misuse negligence or accidents and to items of normal wear and tear to be specifically mentioned by the Contractor in his offer and got accepted by the Employer. The decision of the Employer concerning Contractor's liability and the amount if any payable, under this warranty, shall be final and conclusive.

- **11. Supervision of Electrical Works:** The said works will be supervised by the concerned Officers of the Electrical Wing of WBSEDCL.
- **12. Mode of Measurement:** Measurement of Electrical works should be done by the competent officers of the Electrical Wing of WBSEDCL in Measurement Book according to Priced Schedule and Agreement.
- 13. Specification For 1.1kV Grade PVCA Cables, 650 V Grade PVC Insulated and Sheathed Wiring Cable and Terminations of Power Cables: All power cable shall be procured from reputed manufacturer. The cables must be manufactured under IS: 1554 (part-IT) 1976 and latest amendments thereafter. The supplier also obtains manufacturer's test certificate. The cables even in a smaller length should be supplied in a coil formation either in cable drums or duly protected with proper packing so that the same is not damaged during rough handling in transport or at site on work. The both ends should be properly sealed with PVC caps and adhesive so that no moisture can penetrate in side cables.

Termination of above cables, including supply of suitable brass compression cable glands for respective size of heavy duty type including solder less copper cable sockets (Dowell's make) and necessary anti oxide pest (Dowell's make) required duringcrampingofsocketsbysuitablesectionofcrimpingdiceandtoolsetc.mention may be made that beyond 120 Sq. mm. size hydraulic type machine to be used for propercrimpingofcablesockets. The sockets must be tinned properly and should be cleaned before insinuating the conductors applying anti-Oxide pest for proper surface bondage.

Wiring cable shall be manufactured under IS: 694/1900 or BS: 2004 for PVC insulated sheathed/unsheathed with copper conductor stranded of 1.1KV or 650 volts grade having colour code as required for electrical use.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

14. Power Cables -Laying:

Sizes of cables required are given in the bill of quantities. Only armored and unarmored cables shall be stranded Aluminum conductors, PVC sheathed, 1100V grade conforming to IS; 1554 &694.

Cables are to be laid both inside and outside the buildings. Lying of cables shall be in accordance with IS: 1255. Inside the buildings, cables shall be laid in G. I. pipes / Polythene Pipes of suitable sizes or open trench as required. Outside the buildings, the cables shall be laid in the ground at a depth of 1 meter from the ground level along the approved routes with necessary brick and G.I. protection for vertical riser / road crossings. Lying of cable includes excavation of earth i.e. making the required trench, placing the cables in trenches, providing the necessary sand cushioning below and above the cables and brick protection at top. Identification -

tags shall be provided on the cables at regular intervals where more than one cable is laid. After the laying of cables as approved by the Engineer-in-Charge, the trenches shall -be filled with shifted earth and well rammed to bring the surface in level with the surroundings. SandshallbeofgoodqualityriversandandthebricksBclassburnt.Sandandbricks shall be laid continuously on the cables to cover the cables fully. Cable identification makers made of galvanized steel places incorporating the information such as the line voltage, size of cables. Cable identification no. shall be provided at intervals of 10 meters along with entire cable route in an approved arrangement.

Wherever the cables are crossing the roads, drains, and water/sewerage pipes or entering/leavingthebuildingsthecablesshallbelaidinclassBG.I.pipesofsuitable size as directed by the Engineer-in-Charge.

Straights through joints are not normally permitted. In cases of unusually long distances of cable, laying work straight through joints would be considered on permission only if the kits of specified make are used. No extra payment will be permitted for such joints.

15. Sub Power-Distribution Boards (PDB/EPDB) and Lighting Distribution Boards (LDB/ELDB) Service/Meter Boards and Main Switch Boards: All the PDB/EPDB/LDB/ELDB, Service Meter and Main Switch Boards shall be of robust construction and suitable for flush-mounting /wall mounting type. They must be of industrial heavy duty type, compartmentalized and fabricated out of 14 SWG sheet-steel with MS angles and channels of suitable sizes wherever necessary, totally enclosed, fully gasket, dust and vermin proof, removable top and bottom plates with suitable knockouts at appropriate location for entry of 20.25 and 40 mm dia. PVC/MS conduits, hinged front doors (single or two half doors depending upon the size of the board) with locking arrangements & two earthing terminals etc. to be provided.

Service Meter Boards housing front operated SFUs, terminal blocks, fuse cut-outs, kWh meters etc, shall be provided with suitable arrangements for locking and sealing front door. Suitable cut-outs and glass windows in front of kWh meters shall be provided for taking readings and for periodical watching meters working.

PDB/EPDB, LDB/ELDB service meter boards and main switch boards shall be complete with all the equipment

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

such as MCCBs, MCBs, Isolators, SFUs, Fuse Cut-outs, kWh meters etc. as indicated in the Schedule of Quantities for the incoming and outgoing circuits, suitably rated copper bus bars, neutral links, internal wiring, phenolic phase barriers wherever necessary, clearances between phases, phases-neutral and earth maintained as per relevant IS and properly painted with anti-corrosive primers and finish paints. Finish colour should be as per client'schoice.

16. MouldedCaseCircuitBreaker(MCCB)

MCCBs are required for use in three phases, 400 Volt feeders for "On-load" closing and opening. Current rating shall be as indicated in the Schedule of Quantities. Breaking capacity at 415 V and P. F. between 0.2 and 0.4 shall not be less than 25 KA for 100 A, 35 KA for 200 A, 35 KA for 250 A, 50 KA for 400 A and 50 KA for 630 A rated MCCBs. The MCCBs shall have mechanism for quick make and break operation and provided with thermal magnetic release for short circuit and over current protections. There shall be provision for setting the short circuit tripping between 300% and 800% and over-load tripping between 50% and 100% of the nominal rating in addition to continuous current setting (IR) in 5 steps between 100% and 50% of nominal rating. All the PCCs, MCCs are to be provided with door interlocking arrangements.

A power circuit shall always be originated from a distribution fuse boards and the same shall run in a separate PVC conduit/cable as considered in generalscheme.

Insulated or covered earthing conductors where used, shall have green insulation braiding or covering as appropriate. Under as circumstance shall the colour green be used for other than earthing conductor. In addition, where it is required that cables of different colours be used for identification purposes; the following system shall be employed. Red, Yellow and Blue colour for phases and black for neutralonly.

The electric load of all lights, power outlets etc. shall be balanced across the three phases.

Unless otherwise mentioned in the schedule of quantities, single way porcelain/Bakelite terminal connector with nickel-plated brass pin and screws to suit the conductor. Size shall be used for intermediate wiring joints in junction boxes and switch-boards.

Distribution wiring in PVC conduit casing capping to light, fan, socket outlets, exhaust fan points etc. shall be done in looping in system. In this system except at stopping points such as at terminals of switches, ceilingroses, etc, and in case of socket outlets at the socket terminals. Intermediate wiring joints injunction boxes will not be permitted.

The maximum number of wires drawn in one PVC conduit shall not be greater than the recommended number given in the table of IS. 732-1963, contractor must consult the specification given above.

Sub-mains are considered for the wiring from PDB to power outlets LDBs and point controlswitchboards. These may be by two-core PVCA cable/PVC insulated sheathed copper conductor wires as considered in bill of quantities.

17. Point Wiring in Buildings: Wiring in the buildings shall be concealed /surface drawn. PVC conduits, conduit accessories, PVC casing, capping cables, ceiling-roses, switches etc. used in the wiring shall be of approved makes. All wiring to be done by stranded single core copper PVC cable of sizes 1.5 Sq.mm. for phase and neutral and one sq. mm., copper PVC cables for earth wire (Green colour). In case of rewiring partially, the similar cables are to be used as existing. Laying of conduits, conduit accessories and wiring in concealed and surface system shall meet the requirements of IS-732; National Electrical Code and National Building Code. The PVC and MS

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

conduits shall conform to IS: 9537 (part 1 and 3) and IS: 1653 respectively. Metal junction boxes/PVC junction boxes shall be used with PVC/MSconduitsasthecasemaybe. Conduitaccessories such as junction boxes pullboxes, outlet boxes, bends. Sleeves etc shall conform to IS: 5133. Necessary GI pull wire of 14 SWG shall be provided in the conduits from one end to the other as required for drawing electrical wires.

PVC conduits/Alkathene pipes shall be laid as far as possible in straight runs tied to the reinforcement bars to prevent the getting dislocated during concreting. Where conduits are required to be embedded in the walls, the walls shall be chased to the required depth and conduits fixed in position by means or suitable pipe hoods at every 600 mm distance in an approved manner. The walls chased for conduit embedding shall be covered suitably by the Electrical Contractor. Preparing switch board covers, control switches for all lights, fans, call bells, exhaust fans, ceiling roses, PVC insulated electrical wires, bond wire etc. are parts of Schedules for point wiring. Similarly, conduits laying covered under a separate schedule item include providing and embedding Alkathene pipe/MS conduits in RCC roof slabs/beams, walls, MS junction boxes, bends, outlet switch boxes with 3 mm thick Phylum sheet, fixing brass screws and cup washer etc. in running meter measurement. Switch-boards may be of double teak-wood board with Phylum cover or MS with Phylum cover as the case maybe.

Terminal/outlet/switch boxes shall be of MS sheet of not less than 1.5 mm thick and provided with 4/6/8 threaded holes depending upon the size of the box. The depthoftheboxesshallnotbelessthan75mmandthecenter cross sectional area in between from 100 to 750 Sq. cm. The boxes shall be provided with two coats of anti-corrosive paint and the inside surface finished with suitable white paint. The front cover should be of 3 mm thick colored or white Phylum sheet and over size by 1 cm, all round shall be provided with suitable brass screws & cup-washer for MS Board only.

Sheet Metal Connector Box (16 SWH) of the following sizes with 3 mm thick white Phylum sheet cover is to be used:

- i. 6" x 4" x 2.1/2"
- ii. 7"x4"x2.1/2"
- iii. 8"x6"x2.1/2"
- iv. 4" x 4" x 2.1/2"

In case of surface wiring by casing capping, the double T. W. Switch Board and Junction Box of the following sizes (with 3 mm thick white Phylum sheet cover fixing by four Nos brass wooden screw with Cup-washer) are permitted:

- i. Double T. W. Switch Board: T- x 4" x 2" / 8" x 6" x 2" / 8" x 10" x 2" / 8" x 12" x 2"
- ii. JunctionBox:7"x4"x2"/4"x4"x2"

18. T.W. Round Block (75" mm dia): There shall be 3 mm wide and 3 ram deep- groove cut all round the surface against which the bottom of cover will rest and approved plastic compound shall be filled before fixing it finally.

19.Installation of Switchboard:

These shall be installed at a height of 1.3 meters (4'-3") above the floor level.

Various sizes of wires viz. 1, 1.5, 2.5, 4 and 6 Sq. mm which are required to be used in the wiring of buildings shall be of stranded flat twin/single core copper conductors, PVC insulated &sheathed 1100-volt grade conforming to relevant IS-specification.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

The number of cables/wires drawn in various sizes of conduits shall not exceed the following limit.

650/1100V PVC Copper Wire	In 20mm diameter conduit	In 25mm diameter conduit	In32mm diameter conduit
1.5Sq.mm	4Nos	8Nos	12Nos
2.5Sq.mm	3Nos	6Nos	10Nos
4.0Sq.mm	2Nos	6Nos	8Nos
6.0Sq.mm		5Nos	7Nos
10.0Sq.mm		3Nos	5Nos

20.Brief details of use of specific wire-sizes/switches/sockets are given below:

- a) For light, fan, call bell and Stranded 1.5 Sq. mm single core 6A plug point PVC Unsheathed copper
- b) For connecting air-conditioners Board with 20amp capacity industrial type socket(Crompton/Standard/Havells) with MK-I starter(L&T) with 20 ampere MCB.
- c) All main and sub-main power cables will be of Aluminum armored.
- d) For air-conditioners, in-coming power supply cable will be of 7/0.36 mm stranded size (phase and neutral) and for earth 2.5 sq. mm (3/0.036 mm) stranded single core copper cable from separate way of PDB
- e) Composite 6 in 1 plug-socket board (with following provisions) should be provided in selective areas:
 - i. 16AmpSocket flush type
 - ii. 6Amp Socket flush type
 - iii. Oneswitch16AmpSocketflushtype
 - iv. One fuse flush type
 - v. One indicating lamp flush type
 - vi. 6Ampone-wayflushtypeswitch
- f) Such composite 6 in 1 plug-sockets should be provided in different places as per Guide line. I) All vertical-drops (wiring) should be concealed for horizontal portion only.
- g) In horizontal cases, PVC casing and capping permits surface-drawn wiring. But in new OT both horizontal and vertical wiring should be concealed.
- h) OT switch boards should be water protected as design to be approved by site- m-charge.
- i) For lights/fans/call bells/engaged sign etc. circuit wiring is a part of point wiring. Maximum load per circuit will be 800 watts but number of points should not exceed eight (8) leaving behind two (2) points for future loads.
- **21.Equipments and Fittings:** The type, rating, the required features, location of fixing etc. are indicated in the Schedules. The schedule includes all other required accessories, fasteners, small wiring etc., fixing, aligning, connecting, testing and commissioning. The materials shall be of good quality acceptable to Engineer-in-Charge and to be fixed m position as directed by him.

WBSFDEL

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

- **22. Box/Rail Type Fluorescent Light Fittings:** Both single and twin tube assemblies shall be of standard fittings made out of cold- drawn sheet steel stove enameled, the box finished in grey colour and its cover plates in white colour, complete with copper chokes, starters, starter holder, tube holders, lamps and earth terminal etc.
- 23. **Decorative Type Fluorescent Light Fittings**: Similar to 7.2. with opal acrylic diffuser Mirror Optics Type Fluorescent Light Fittings Both single and twin tube assemblies shall be of standard fittings made out of cold-drawn sheet steel, stove enameled, the box finished in grey colour and its cover plates in white colour, complete with copper chokes, starters, starter holder, tube holders, lamps and earth terminal etc. with mirror reflector.
- 24. Compact Fluorescent Type Light Fittings: Compact fluorescent fitting with 2 x 1 1 Watts lamps, holders, stainless steel reflector with housing and OPEC Street Light (TFL) Fittings. The fittings shall be SON/70W/150W or weather proof type fluorescent street light fittings. The fittings shall be made of Aluminum sheet and finished outside in hammer tone grey colour, stove Enameled and white inside complete with copper wire chokes, starters condensers, suitable lamp. Control switches for lights, fans, call bells, exhaust fans etc. shall be of rating 6 Amps, 230Voil, Piano-type flush mounted, cream colour conforming to relevant Indian Standards. Ceiling roses also shall be of 6 Amps, rating 230 V. cream colour deluxe conforming to the relevant IS Specification Switches of 16 Amp capacity and associated 16A socket would also be required to provide facility of connection of power load upto 1 kW. Alternatively, Industrial type plug-socket board may be used in specific cases. Cable used for power load should be of suitable capacity.

After successful completion of the work, the final drawing/Blue Print Plan showing the details circuit diagrams and fittings, fixtures are to be submitted along with the final bill.

25. Earthing: All non-current carrying metal parts of the electrical installations such as switch gears, LT panel, distribution boards, power plugs, exhaust fans, air conditioners, cable glands, MS conduits, switch boxes etc. shall be bounded together suitably and connected to earth-stations in accordance with the requirements of Indian Electricity Rules and IS:3043.All earth stations shall be of the same type similar to one illustrated in IS: 3043, usingpipeelectrodeofgalvanizedsteelClassBhaving65mmdiaandalengthof3.04 meter buried vertically in the ground and providing layers of charcoal/coke and salt as necessary. The top end of the pipe electrode shall have suitable arrangements for making connections of earth wire/flats in the manner approved by the Engineer-in Charge. The earth stations snail be located at least 2 M away from the buildings and not less than 6 M apart. Nearby earth stations (at least two) shall be interconnected with suitable size GI flat. The earth inspection pit should be provided with brick and cement work of 254 mm (10") thick with 1st Class bricks in cement mortar (6:1) both inside and outside plastered 19 mm (3/4") thick and including neat cement finish 1.6 mm in thickness both inside and top outside & C. 1 manhole 0.46 Mt. dia. complete with C. I. cover (weight being 32 kg) fixed flush with ground surface. The inside dimension whenfinishedshouldbe0.60mx0.60m(2x2)and0.40m(1-3"indepth).

26. Earth connections shall be as follows:

i. For building wiring the earth lead will be drawn from earth electrode to earth bus-bar by 19/10 G.L

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

stranded wire and from earth bus-bar to PDB 8 SWG GI wire & from PDB to, SDB & LDB etc. by No. -10 SWG G.I wire. For Power plug and 6 Amp plug, either by 1 Sq. mm stranded copper/l6 SWG G.I. wire as the case may be which will be mentioned in B.O.Q.

- ii. Double connections shall be made for medium voltage supply.(251to650V).
- iii. All earth wires and flats from one end to the other shall be continuous and without any joints and so laid to protect them against mechanical damage.
- iv. If the required earth resistivity is not obtained with the earth-pits, additional pits shall be ma3e for improving the system resistivity. The rates payable for additional pits shall be same as the rates quoted in the tender.
- v. Earthing Schedule includes supply of all required material, digging pits, providing charcoal / cake and salt, filling up the pits (providing cement concrete chamber withcoverforsubstationearthingonlyforlayingofearthwires/flatmaking.
- vi. Connection with proper fasteners, finishing machinery works that have been disturbed for electrical works, testing etc.

27.Erection of Poles: Erection of single steel tubular pole of length, as given below with or without sole plate & cap etc. in cement concrete foundation (proportion and dimension indicated below) as to G. S. having 600 x 600 x 150 mm thick cement concrete (4:2 1) base blockbelowsoleplate/PolewithhardMamametalincludingCC(6:3:1)muffingof0.3 Mt (3ft) dia and 0.3 Mt (1 ft) above ground level including 3 mm (1/8") thick neat cemented finish and providing G. I. earth bolt after making drilled holes etc. on pole &carnage of pole up to 1 .6 km. from store depot to work site including filling up the excavated earth pit with shifted soil and ramming properly.

 Dimension of Poles
 Proportion
 Dimension

 1) Upto 9 Mts,
 6:3:1
 0.6x0.6x 1.70 Mt.

 a) Above 9 Mt.
 6:3:1
 0.6x0.6x 1.91 Mt.

acrylic diffuses etc. of SIGMA' search light makes.

ErectionofH-pole(D.P.)structurewith9Mt.longsteeltubularpoles(0.9Mt.to1.5 Mt. apart) in cement concrete (6:3:1) foundation, (as to similar dimension in item1.2(above)including600x600x150mm.(2'x2'x6")thickcementconcrete (4:2:1) base block below sole plate / pole with hard jhama meta) including cement concrete (6:3:1) muffing 300 mm. (1 ft.) dia. and 300 mm above ground level neatly cemented finish 3 mm (1/8") thick and providing galvanized MS channels, cross arms and cross bracing made out of galvanized, angle, flats etc. anti-climbing devices, 'Danger' board & earth bolt etc." as per IS code of practice.

Extension items 1 & 2 above, for providing cement concrete (6:2:1) base block (around the pole) dimension 0.60 x 0,60 x 0.76 Mt. (2" x 2" x 2'-6") above ground level, neatly cemented finish (3 nun thick) at the base of pole (in lieu of cement concrete muffing) including S & f looping cable box 25 cm x 25 cm x 0 cm (1 0" x 1 0" x 4") made of C.I. &including providing drilled hole in pole suitable for Alkathene/polythene pipe entry as directed for street lightwiringPaintingofSteelTubularPoleoflengthsandno.ofcoatsofpaintasgivenbelowwith readymixedpaint/primerofapprovedmakebrandincludingpreparationofsurfaceby sand paper/ emery paper, cleaning etc. for receiving fresh coat of paint. Painting block letters or digits within a circle/square as required with "Black Japan" paint of approved make & brand the size of letters and digits.

(A Govt. of West Bengal Enterprise)
MALDA REGIONAL OFFICE

Administrative Building, WBSEDCL, 1st Floor, Rabindra Avenue, Malda, WB- 742101.

E-mail: rm.malda@wbsedcl.in

Regd. Office of WBSEDCL: VidyutBhavan, Block-DJ, Sector – II, Bidhannagar, Kolkata – 700 091. Website-www.wbsedcl.in

CIN: U40109WB2007SGC113473

Painting of Steel Tubular pole of lengths and no. of coats of paint as given below with ready mixed paint/primer of approved make &brand including preparation of surface by sand- paper/emery paper, cleaning etc. for receiving fresh coat of paint.

Painting of any steel/iron surface with no of coats of paint as given below with ready mixed paint/primer of approved make and brand including preparation of surface by sandpaper, cleaning etc. for receiving fresh coat of paint. Street light as described in bill of quantities. The Schedule item of street light poles include manufacture of stepped poles, excavation of pits, making concrete foundations, erection of poles, filling up of pits satisfactorily, fixing of light fittings on poles, connection with suitable weather proof insulated wires, earthing, testing and commissioning at the locations decided by the Engineer-in-Charge. The pole shall be as per the sketch enclosed. The poles shall be manufactured out of steel tubes conforming to IS: 2713 as shown in the drawing. There shall be a base plate of MS of size 220 x 200 x 6 mm weldedtothebottomofthepoleandoneMSrodof19/20mmdia and300mlonginserted across the pole and welded at a height of 600 mm from the base plate and both of them coated with black bituminous paint. The cable terminal arrangement shall be built in within the MS sleeve loop box as per in the sketch. Water light 2 ram thick MS box shall have locking arrangement to house two sets of terminals for incoming and looping connections and one re-wire able fuse fitting with 6 Amps fuse fixed on 6 mm thick phylum base & properly insulated

weatherconditions. The poles shall be erected properly with cement concrete foundations as per P.W.D. (ELECT) specification- Necessary cutting of the concrete shall be done as per relevant procedures. Two P. V. C. pipe of not less than 30 mm dis. with gland and bends shall be provided in the foundation for cables entry into terminal box. Electrical connection between the terminal box and the light fitting shall be made by means of 2.5 mm single core, PVC insulated copper cable of 1100V grade.

28.MODE OF MEASUREMENT: Measurement of Electrical works should be done by the competent officers of the Electrical Wing of WBSEDCL in Measurement Book according to Priced Schedule and Agreement.

29. THE FOLLOWING INDIAN STANDARD CODES ARE APPLICABLE

- 1. IS: 732/1989 Code of practice for elec. installation.
- 2. IS:1646-1961-CodeofpracticeforsafetyofBuilding(GeneralElectricalInstallation)
- 3. IS: 3646 Part -I Code of practice Principles Part H and Port m for good lighting and aspects of design, schedule for values of illumination and glare level and calculation of Coefficient of utilization.
- 4. IS: 4347-Code of practice for Hospital lighting.
- 5. NEC 1985 National Electrical Code for hospital and-Operation Theatre.
- 6. IS: 3480 Flexible Steel Conduits for Electrical Wiring
- 7. IS: 2667 Fittings for rigid Steel Conduits for Electrical Wing
- 8. IS:3837-AccessoriesforrigidSteelConduitsforElectrical Wiring.
- 9. IS: 9537 Part-Hi- 1983-PVC Conduits for Electrical wiring.
- 10. IS:694-1977-Specifications for PVC insulated Cable for working voltage upto and including 1100Volts.
- 11. IS: 8130-1984-Specification for Conduits for insulated Electrical Cable and Flexible Cords.
- 12. IS: 5563 -Electrical Power Connectors.
- 13. IS: 3854-19S8 Flush type switches.
- 14. IS: 1293-198S 3Pin Sockets.
- 15. IS:6538-1971-3pinpianotop.
- 16. IS: 371-1979-CeilingRoses.
- 17. IS: 374-1979-CeilingFan.