

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

Division Office:
Nakashipara Division
Supermarket, P.O. Bethuadahari,
Dist. Nadia, Pin 741126
Email: dm.nakashipara@wbsecl.in



OFFICE OF THE DIVISIONAL MANAGER NAKASHIPARA DIVISION

Registered Office:
Vidyut Bhavan, Block -DJ
Sector-II, Bidhannagar, Kolkata - 700 091
CIN - U40109WB2007SGC113473
Website- www.wbsecl.in

NIT No. : NKPD/DM/Tender/(22-23)/15
Memo No. : NKPD/DM/Tender/ 773

TENDER NOTICE

Dated: 01.09.22
Dated: 01.09.22

To

Sub: To offer rate for Erection of 33 KV Bay along with Erection of 33 KV Gantry-cum-Isolator support structure, 33 KV CT, 33 KV VCB and allied works at Muragacha 33/11 KV Sub-Station for incoming 33 KV line from Debagram GSS under Nakashipara Division .

Dear Sir(s),
Sealed tenders with Firm's own seal are invited from the contractors who have credential in doing such installation work in W.B.S.E.D.C.L. to offer rates for the schedule of work furnished in separate sheet enclosed here with. Tenders will be received on 14.09.2022 up to 2.00 p.m. and the same will be opened at 2.30 p.m. on the same date in presence of attending tenderers'. Reference of enquiry and due date of submission should be prominently written on the envelop. The work will be carried out as per Company terms and conditions and as per I.E. Rules.

Terms and Conditions:

1. Tender Notice number with date of issue of enquiry & the date of submission of the tender should be prominently written on the envelope.
2. Eligibility Criteria : All categories of intending Tenderers who have successfully completed at least 50% of estimated value of Rs. 286998.83 (Rupees two lakhs eighty six thousand nine hundred ninety eight and eighty three paise only.) approximately of the said tendered items to WBSEDCL / other Power Utilities / other Govt. departments against Purchase Orders, Inspection Offer Letters (if any), Delivery Instructions (if any), signed challans etc.
3. The tender shall quote the price both in figure & in words.
4. PAN, GST Registration No., is to be submitted with the offer.
5. Quotation should be as per specification mentioned in the tender notice.
6. Bidders are requested to mention proper contact details (i.e. Mail ID, Phone no & Mailing Address) in their Quotation for Official communication process. Absence of communication details may lead to cancellation of Quotation.
7. Controlling Officer: The Divisional Manager, Nakashipara(D) Division will be the controlling officer of the work while the Assistant Engineer (Tech), Nakashipara(D) Division will be the Site Engineer in charge.
8. Paying Officer: The Assistant Manager (F&A), Nakashipara(D) Division will be the Paying Officer of this work who will release payment against bill certified by the Site Engineer and the Controlling Officer.
9. Scope of Work: All work should be carried out in compliance and in accordance with the approved specification/drawing and as per direction of the Controlling Officer/Site Engineer of the work. The Company reserves the right to reject or accept any of all tenders without assigning any reason whatsoever. The total amount should be given in figures and words. The work may be varying $\pm 10\%$ of the schedule of work. The work schedule is enclosed herewith.
10. Supply of materials: 33 KV CR Type Isolator, 33 KV VCB's, 33 KV C.T.'s, 42 KV L.A.'s, 1.1 KV grade 2.5 Sq. mm. Copper Control Cable 4 Core & 8 Core, ACSR 200 Sq. mm. Panther Conductor, required sizes M.S. Iron Sections like Channel, Angle & Flat, different type Connectors etc. will be supplied by WBSEDCL. Required Nuts & Bolts, L.A. Base Plate. G.I. Flat 50X6 mm., Sand, Brick, Chip Stone, Cement etc. have to be supplied by you. Necessary arrangements for welding of iron section have to be provided by you.
11. Tools & Tackles: All the Tools & Tackles required for such work, you should supply for completion of the work in time.
12. Custody of material: You shall be entirely responsible for all the materials issued to you for the work and the executed portion of the work till it is officially taken over by the Company.
13. Completion Time: The work will have to be completed within 25 (Twenty five) days from the date of placement of Order. This should be treated as an essence for the contract. Delay in completion will attract penalty @ $\frac{1}{2}\%$ value of order for each day of delay to a maximum of 10% value of order.
14. Guarantee: You will be responsible for 12 (Twelve) months from the date of handing over the installation for any defects arising on the aforesaid work. In case you fail to rectify the defects within 15 (Fifteen) days from the date of notification of defects, the company shall have the liberty to execute the same on your behalf through the assistance of other agency or undertake departmentally and the cost incurred thereof will be adjust from your security and other pending bills.
15. Security Deposit: 10% of value of the order will be deducted from your bill as security deposit which will be refund after expiry of guarantee period of 12 (Twelve) months from the completion of work.
16. Shutdown & Accident: Proper shutdown permit should be obtained from the A.E. (T), Nakashipara Division as and when required. The Company should neither be held responsible nor will be liable to pay any compensation for any accident caused to any of your workers or to any member of the public arising out of the execution of the work and/or executed portion of the work, till it is officially taken over.
17. Site/ Spot: Before quoting the rate you must visit the spot contacting with the Site Engineer.
18. You shall be responsible for compliance of the entire statutory obligation as included in the following Acts:
(a) Contract Labour (Regulation & Abolition) Act, 1970, (b) Workmen compensation Act, 1923, (c) Minimum Wages Act, 1948 read with the current wages as directed by the Joint Labour Commissioner, West Bengal vide his order no. 345/350/RW/LCS dt. 31.7.06, (d) Payment of Wages Act, 1936, (e) Payment of Bonus Act, 1965 and (f) Employees Provident Fund and miscellaneous provisions Act, 1952.

Yours faithfully,

(D. Bairagi)

D.E. & Divisional Manager
Nakashipara(D) Division

WEST BENGAL STATE ELECTRICITY DISTRIBUTION COMPANY LIMITED

(A Government of West Bengal Enterprise)

**OFFICE OF THE DIVISIONAL MANAGER**

Registered Office:

Vidyut Bhavan, Block -DJ

Sector-II, Bidhannagar, Kolkata - 700 091

CIN - U40109WB2007SGC113473

Website- www.wbsedcl.in

Division Office:

Nakashipara Division

Supermarket, P.O. Bethuadahari,

Dist. Nadia, Pin 741126

Email: dm.nakashipara@wbsedcl.in

NIT No. : NKPD/DM/Tender/(22-23)/15

Memo No. : NKPD/DM/Tender/ 773

Dated: 01.09.22

Dated: 01.09.22

Schedule of works for Erection of 33 KV Bay along with Erection of 33 KV Gantry-cum-Isolator support structure, 33 KV CT, 33 KV VCB allied works at Muragacha 33/11 KV Sub-Station for incoming 33 KV line from Debagram GSS under Nakashipara Division .

Sl. No.	Description of works	Unit	Quantity	Rate per unit in ₹	Total in ₹
1	ERECTION OF GANTRY STRUCTURE WITH PROVISION FOR ISOLATOR AND LA ,WITH FOUNDATION ALONG WITH SUPPLY OF ALL NUTS AND BOLTS AND LA BASE PLATE 430*430*8 MM	NOS	1		
2	ERECTION OF H/L BUS SUPPORT STRUCTURE WITH FOUNDATION & SUPPLY OF ALL NUTS AND BOLTS	NOS	2		
3	ERECTION OF L/L BUS SUPPORT STRUCTURE WITH FOUNDATION & SUPPLY OF ALL NUTS AND BOLTS	NOS	2		
4	ERECTION OF C.T. STRUCTURE	NOS	1		
5	ERECTION OF 33KV,400A,CENTRE ROTATING ISOLATORS H.L. WITH E.S.	SET	1		
6	ERECTION OF 33KV,400A,CENTRE ROTATING ISOLATORS H.L. WITHOUT E.S.	SET	1		
7	ERECTION OF 33KV,400A,CENTRE ROTATING ISOLATORS L.L. WITHOUT E.S.	SET	1		
8	ERECTION OF 33 KV VCB,SCADA COMPATIBLE	NOS	1		
9	ERECTION OF 33KV,C&R PANEL,SCADA COMPATIBLE FOR FEEDER CONTROL WITH DIRECTIONAL RELAY	NOS	1		
10	ERECTION OF 33KV, DUAL CORE , DUAL RATIO,400-200/1-1 AMP C.T.	NOS	3		
11	LAYING & JOINTING OF 1.1 KV 4C*2.5 SQ. MM COPPER CONTROL CABLE WITH SUPPLY OF CABLE LUGS,GLANDS,TAPES,SOCKETS ETC	KM	0.16		
12	LAYING & JOINTING OF 1.1 KV 8C*2.5 SQ. MM COPPER CONTROL CABLE WITH SUPPLY OF CABLE LUGS,GLANDS,TAPES,SOCKETS ETC	KM	0.48		
13	ERECTION OF 42KV CLASS GAPLESS LIGHTNING ARRESTER	NOS	3		
14	INSTALLATION OF C.T. JUNCTION BOX	NOS	1		
15	EARTHING(INCLUDING SUPPLY OF MATERIALS)	JOB	1		
16	ERECTION OF 12.8 MTR RAIL POLE	NOS	2		
17	ERECTION OF ACSR 50 SQ. MM CONDUCTOR (1-WIRE) INCLUDING LAYING,HOISTING,JOINTING ETC	KM	0.05		
18	ERECTION OF ACSR 200 SQ. MM CONDUCTOR (3-WIRE) INCLUDING LAYING,HOISTING,JOINTING ETC	KM	0.025		
19	FIXING OF 33 KV PIN INSULATOR WITH PIN	NOS	18		
20	FIXING OF 33 KV DISC INSULATOR WITH PIN	NOS	12		

Signature of Tenderer
(With Seal)

D.E. & Divisional Manager
Nakashipara (D) Division